

Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand.

NIB Number: 03/JREDA/OFFGRID/RC/26-27

JREDA

Government of Jharkhand



Jharkhand Renewable Energy Development Agency (JREDA)

3rd Floor, S.L.D.C. Building, Kusai Colony, Doranda, Ranchi-834002.

Ph.: 0651-2491161, Fax: 0651-2491165,

E-mail: info@jreda.com; Website: www.jreda.com

CONTENTS

Sl. No.	Description	Page No.
1	e-Procurement Notice	03
2	Section-1 List of Important dates & details of Bids	04
3	Section-2 Instruction to Bidders	05
4	Section-3 Notice Inviting Bid	07
5	Section-4 Instruction to Bidders	13
6	Section-5 General Terms & Conditions	25
7	Section-6 Technical Specification	30
8	Annexure-1 (Covering Letter)	48
9	Annexure-2 (Checklist for Technical Bid)	49
10	Annexure-3 (Information about the Bidding Firm)	50
11	Annexure-4 (Declaration by the Bidder)	51
12	Annexure-5 (Annual Turn Over)	52
13	Annexure-6 (Net Worth)	53
14	Annexure-7 (Power of Attorney for Signing Bid)	54
15	Annexure-8 (Details of Work Experience)	55
16	Annexure-9A (Price Bid)	56
23	Annexure-9B (Price Break up)	57
17	Annexure-10 (Undertaking by MSEs of Jharkhand)	61
18	Annexure-11 (Certificate of Material Delivery-Mini Grid)	62
19	Annexure-12 (Certificate of Installation-Mini Grid)	63
20	Annexure-13 (Format for O&M and CMC report-Mini Grid)	64
21	Annexure-14 (Performance Guarantee Testing Report Format)	65
22	Annexure-15 (Warrantee Card)	66
26	Annexure-16 & 17 (Declaration by the Bidder)	67
27	Annexure-18 (Monthly Generation Data)	69
28	Annexure-19 (Site Survey Checklist)	70

Govt. of Jharkhand
Energy Department
Jharkhand Renewable Energy Development Agency (JREDA)
3rd Floor, S.L.D.C. Building, Kusai Colony, Doranda, Ranchi-834002.
Ph.: 0651-2491161, Fax: 0651-2491165,
E-mail: info@jreda.com; Website: www.jreda.com

e-Procurement Notice

Tender Reference No.: 03/JREDA/OFFGRID/RC/26-27

Dated: 21.04.2026

1	Name of the work	Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand
2	Period of contract	05(Five) Years
3	Time of completion	04 (Four) Months
4	Date of publication of NIT on website: http://jharkhandtenders.gov.in	30.04.2026 (Thursday)
5	Last date & time for receipt of online bids	25.05.2026 (Monday) upto 05:00 PM
6	Submission of Bid fee & EMD through Online via SBI Payment Gateway of Jharkhand Tenders.	25.05.2026 (Monday) upto 05:00 PM
7	Technical Bid Opening Date	28.05.2026 (Thursday) at 3.00 P.M.
8	Name & address of office inviting tender	Director, Jharkhand Renewable Energy Development Agency (JREDA) 3 rd Floor, SLDC Building, Kusai, Doranda, Ranchi- 834002 (Jharkhand)
9	Contact no. of procurement officer	0651-2491163/61/7004806449
10	Helpline no. of e-procurement	0651-2491163/61

**Any corrigendum/addendum can be seen on website: <http://jharkhandtenders.gov.in> & www.jreda.com.
Further details can be seen on website: <http://jharkhandtenders.gov.in> & www.jreda.com**

Sd/-
Director,
JREDA, Ranchi

Section -1

NIB No: 03/JREDA/OFFGRID/RC/26-27

List of Important dates & details of Bids

1.	Name of work	Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand
2	Tender reference no.	03/JREDA/OFFGRID/RC/26-27
3	Contract period	05 (Five) Years
4	Mode of submission of tender	Online through www.jharkhandtenders.gov.in
5	Cost of Bid document (Non-refundable)	<ul style="list-style-type: none">• Rs.11,800/- Inclusive GST for General Bidder.• Rs. Nil for MSMEs of Jharkhand (Manufacturing Sector)• Note: Submission of Bid fee through Online via SBI Payment Gateway of Jharkhand Tenders.
6	Earnest Money Deposit	<ul style="list-style-type: none">❖ For General Bidder: Rs. 4.00 Lakhs .❖ For MSEs of Jharkhand (Manufacturing Sector): Nil.❖ Note: Submission of EMD through Online Via SBI Payment Gateway of Jharkhand Tenders.
7	Publishing on website	30.04.2026 (Thursday)
8	Date and Time of Pre-Bid meeting	08.05.2026(Friday) at 12.00 PM
9	Period of downloading of bidding documents	Start date: 01.05.2026 Time: 10.00 AM End date: 25.05.2026 Time: 05.00 PM
10	Bid online submission	Start date: 11.05.2026 Time: 11.00 AM End date: 25.05.2026 Time: 05.00 PM
11	Technical bid opening date	28.05.2026 (Thursday) at 3.00 P.M.
12	Authority inviting bids	Director, Jharkhand Renewable Energy Development Agency(JREDA)
13	Address of office inviting tender	Jharkhand Renewable Energy Development Agency(JREDA) 3rd Floor, SLDC Building, Kusai, Doranda, Ranchi- 834002. Ph.No: 2491161,Fax No: 0651-2491165 Web site: www.jreda.com E-mail: info@jreda.com

NOTE** Only electronic receipt of Cost of Tender and Earnest Money Deposit (Bid Security) will be acceptable as per provisions of Standard Operating Procedure (SOP). Issued by Information Technology & e- Governance Department, Government of Jharkhand Vide Order Memo No. 120, Dt. 03.10.23 of Secretary, Information Technology & e- Governance Department, Government of Jharkhand.

Section-2

NIB No: 03/JREDA/OFFGRID/RC/26-27

Instructions to Bidders

Detailed instructions & documents to be furnished for online bidding

1. The guidelines to submit bid online can be downloaded from website <http://.Jharkhandtenders.gov.in>
2. The interested bidders can download the bid from the website "<http://Jharkhandtenders.gov.in>".
3. To participate in bidding process, bidders have to get 'Digital Signature Certificate (DSC)' as per Information Technology Act-2000 to participate in online bidding. This certificate will be required for digitally signing the bid. Bidders can get above mention digital signature certificate from any approved vendors (CCA). Bidders, who already possess valid Digital Certificates, need not to procure new Digital Certificate.
4. The bidders have to submit their bids online in electronic format with digital Signature. The bids without digital signature will not be accepted. No proposal will be accepted in physical form.
5. Bids will be opened online as per time schedule mentioned in section 1
6. Bidders should get ready with the scanned copies of cost of documents & EMD as specified in the tender document. Before submission of online bids, bidders must ensure that scanned copy of all the necessary documents have been attached with bid.
7. Only electronic receipt of Cost of Tender and Earnest Money Deposit (Bid Security) will be acceptable as per provisions of Standard Operating Procedure (SOP). Issued by Information Technology & e- Governance Department, Government of Jharkhand Vide Order Memo No. 120, Dt. 03.10.23 of Secretary, Information Technology & e-Governance Department, Government of Jharkhand.
8. Uploaded documents of valid successful bidders will be verified with the original before signing the agreement. The valid successful bidder has to provide the originals to the concerned authority. The department will not be responsible for delay in online submission due to any reason.
9. All the required information for bid must be filled and submitted online.
10. Other details can be seen in the bidding documents.
11. **Submission of rate/price-bid in any form by the bidder in technical section shall lead to rejection of bid.**
- B. Details of documents to be furnished for online bidding:
12. **Scanned copies of the following documents to be up-loaded in pdf format on the website <http://Jharkhandtenders.gov.in>.**
 - i. Tender fee through online Mode
 - ii. EMD through online mode
 - iii. Latest GST certificate and GST Returns.
 - iv. PAN Card.
 - v. Firm registration certificate
 - vi. Certificate/documents related to MSEs of Jharkhand as specified in clause I of section 3 and Annex-11 (only applicable for the bidder who wants to avail benefit reserved for MSEs of Jharkhand) Proof of completion of similar works during the last 7 years and list of similar works in hand in the prescribed formats duly signed by the competent authority of the issuing Department.)

- vii. Audited financial Report for the last 3 financial years i.e. audited Balance sheet & P/L (FY2022-23, FY2023-24 & FY 2024-25) certified by chartered Accountant.
 - Viii. ITR for AY 2023-24 ,2024-25 & 2025-26)
 - ix. Annual Turnover Details certified by Chartered Accountant.
 - x. Net worth certificates certified by Chartered Accountant
 - xi. List of current litigant cases in which the bidder is involved.
 - xii. An affidavit for non-engagement of related persons.
 - xiii. Test Certificates for PCU, Battery and Module as applicable which shall be issued by MNRE approved/accredited Test Labs.
 - xiv. For Claiming benefit of MSEs of Jharkhand, valid test reports must be submitted highlighting that the manufacturing unit is located within the state of Jharkhand & must be manufacturer of any one of the major components i.e.(Module/Battery/PCU) issued by any test center approved/recognized by MNRE/test labs accredited by NABL and approved by BIS
 - xv. Authorized address & contact numbers of the bidder as per instruction in the Notice Inviting Bid duly digitally signed
 - xvi. Undertaking of Bidder that he is able to invest minimum of cash up to 10% as defined in ITB
 - xvii. Undertaking for validity of bid for 180 days.
 - Xviii. Copy of written power of attorney of the signatory of the Bid for bidding
13. Scanned Copies of the Annexure as per the enclosed formats should be uploaded after converting the same to .pdf format.
- i. Annexure-1: Covering letter.
 - ii. Annexure-2: Checklist for Technical Bid.
 - iii. Annexure-3: Information about the bidding firm
 - iv. Annexure-4: Declaration by the bidder.
 - v. Annexure-5: Average Annual Turnover certificate issued by CA.
 - vi. Annexure-6: Net-worth certificate issued by CA.
 - vii. Annexure-7: Format for power of attorney for signing of bid.
 - viii. Annexure-8: Details of Orders Received and Executed in Last 7 Years
 - ix. Annexure-10: Undertaking by MSEs of Jharkhand
 - x. Annexure-16 & 17: Declaration by the bidder.
 - xi. Registration Certificate: Contractor Registration Certificate
 - xii. Online Payment Details (UTR Number, Bank Name, Tender fee & EMD Fee) eProcurement system Government of Jharkhand.
 - xiii. Valid and duly registered Electrical Contractor License
14. **Duly filled in & digitally signed Price Bid.**
15. Uploaded documents of valid successful bidders will be verified with the original before signing the agreement. The valid successful bidder has to provide the originals to the concerned authority on receipt of such letter, which will be sent though registered post.
16. Bank Account Mandate form from the Banker.
17. SBD is not to be uploaded by the bidder. The bidder has to submit Self certified stating agree that they agree to the SBD terms. Who disagree on the conditions of SBD, cannot participate in the tender.

Section-3

NIB No: 03/JREDA/OFFGRID/RC/26-27

Sub: Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand

Preamble:

As part of Rural Electrification Program, JREDA invites bid for **“Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different PVTG villages anywhere in the state of Jharkhand ”** for short listing of experienced & eligible Agency to whom work shall be allocated for successful execution of the project in a defined time frame.

(I) General Requirement:

1. The bidder should be a registered company/ Proprietorship/LLP/ Partnership/ /Firm/ Corporation in India. **Authorized dealers’ companies/firms/ corporations and subcontractors are not eligible to participate.**
2. **Bidders claiming benefit of Micro & Small Enterprises (MSEs) of Jharkhand: -**
 - i. The manufacturing or Service unit is located within the State of Jharkhand.
 - ii. The Head Office **or** Corporate Office of such registered unit/company/enterprise is within the territorial jurisdiction of Jharkhand.
 - iii. “MSE is registered with the Directorate of Industries/District Industries Centre, Khadi and Village Industries Board, Directorate of Handloom, Sericulture and Handicraft of Jharkhand Govt, Industrial Area Development Authorities and National Small Industries Corporation Ltd **or** any other body specified by Directorate of Industries, Jharkhand Govt from time to time and other industrial units/enterprises which have submitted IBM and been issued Date of Production (DOP) certificate by GM, DIC/MD, Industrial Area Development Authorities/Director, Industries, GoJ **or** MSEs having Udyog Aadhar Number issued by Ministry of Micro, Small and Medium Enterprises, GoI to be duly verified, whether unit is existing/functional and doing regular production at what capacity by GM, DIC/MD, Industrial Area Development Authorities/Director, Industries, GoJ”.
 - iv. The MSEs /other Enterprises and units must be registered under Jharkhand Goods and Services Tax (JGST) Act-2017 or The Central Goods & Services Tax (CGST) Act 2017.
 - v. The MSE /other enterprise and unit must have encouraged local people in employment.
 - vi. The MSE /other enterprise and unit must have complied with all statutory and legal formalities of concerned regulators/Act.
 - vii. The MSE Unit availing preferential treatment will give an undertaking with respect to point i to vi above including a categorical statement that the product/services being supplied to Govt. Dept. or its agencies has been manufactured/created by the unit located in Jharkhand only, giving details of batch no./date or any other identifiable tag (GSI etc) as per prevalent established practice and will have to submit compulsorily duly signed copy of Form GSTR-9C (For units having aggregate yearly turnover of more than 2 crores) as prescribed under JGST Act-2017”.However, in case of VAT products/services, Form JVAT-409 (For units having of gross yearly turnover more than 60 lacs) issued by dept. of Commercial taxes, Govt. of Jharkhand.

- 3.** The bidder should be a functional organization. To substantiate this claim, the bidder should submit the copy of Audited accounts for last 3 Financial years i.e. audited Balance sheet & P/L for FY 2022-23, 2023-24 & 2024-25 along with Income Tax Return (ITR) for AY 2023-24, AY 2024-25 & AY 2025-26 complete set. These audited accounts should be duly certified by the Statutory Auditor with his stamp.
- 4.** Registered Micro & Small Enterprises (MSMEs) of Jharkhand should submit the attested copy of Registration certificate/ Udyog Aadhar/Udyam issued by the Industry Department, Govt. of Jharkhand duly verified by concerned DIC.
- 5.** The bidder should have valid GST and PAN.
- 6.** Bids from joint venture are not allowed.
- 7.** The bidder must be in house manufacturing & testing facility & should be suitable equipment to perform testing in house, if bidder have not facility to perform such tests, they need to arrange Lab test facility for the samples in the presence of JREDA or JREDA Representative/ Authorized Third Party and the cost of Lab Testing will be bearded by the Manufacturer. All the expenses for inspection in this regard shall be borne by the Bidder only.
- 8.** Contractor Registration in JREDA is mandatory to participate in this tender.
- 9.** Participating Bidder Must possess a valid registered Electrical Contractor license in the appropriate category.
- 10.** Participating Bidder Must Possess Electrical Connection under LTIS (Low Tension Industrial Supply) category as per norms of the Jharkhand State Electricity Commission (JSERC) Supply Code and tariff regulations as applicable for small industries and workshops and Manufacturing Units.
- 11.** For Participating Bidder, the appliances to be Provided for Installation and Commissioning must be of reputed Companies make such as Solar PV modules, Battery, PCU etc.
- 12.** JREDA reserves right to take the necessary decision to award the work in respect to those Agencies who were awarded the work earlier and has not carried out Comprehensive Maintenance Contracts (CMC) regularly and properly with respect to such awarded work
- 13.** Bidders shall have to disclose their office address along with details of their maintenance stock for carrying out AMC (Annual Maintenance Contract) or CMC (Comprehensive Maintenance Contract) work after installation.
- 14.** The Successful bidder shall supply such Solar Components namely solar modules, batteries, and PCU etc. for installation and commissioning that are only manufactured by reputed and trusted companies /make with proven track record. JREDA reserves the right regarding issue of suitable guidelines from time to time in this regard. Such make or model of Solar Components which have been used in the ongoing work in the last five years in JREDA with quality and performance related issues may be avoided by the successful bidder.
- 15.** Successful bidder who are awarded to work, shall at the time of Submission of bill for payment, be required to submit valid E-Way Bill as per GST Act & Rules for verification to authenticate the invoices raise. Further, Bidder is bound to co-ordinate with Work Incharge/JREDA representative for sharing of necessary details for verification of E-Way Bills etc. as and when required.

(II) Commercial Requirement:

1. Turnover certificates:

For General Bidder/MSEs Bidder: Average Annual financial turnover during the last 3 years (FY 2022-23, 2023-24 & 2024-25 certified by chartered Accountant & it should be 30% of estimated cost of minimum lot size. Require Turnover as per given below: -

Sr. No.	Group	Require Turn Over	
		For General category (In cr)	For MSEs category (In cr)
1	Group "A" 1 to 10 kWp With Battery System) Min Quoted -100kWp	0.62	0.21
2	Group "B" 11 TO 50 kWp With Battery System) Min Quoted -250kWp	1.55	0.52
3	Group "C" 51 to 100 kWp with Battery system Min Quoted -500kWp	3.10	1.03
4	Group "D" Above 100 kWp (With Battery System) Min Quoted -500kWp	3.10	1.03

The certificate should be issued by CA with UDIN no. as per the Performa given at **Annexure-5**.

NOTE-Average Turnover in same proportion for higher quoted quantity**

For New-MSEs of Jharkhand: The New MSME is defined as MSME which have not completed 3 financial years from the date of establishment of Solar PV equipment manufacturing unit such as Module/ Cells/ Batteries / PCUs / Any Other Solar PV electronics.

- a. Unit has not completed 1 Year – Financial Soundness Certificate issued from Bank is required not less than 10% of Project Cost / Quoted Quantity Cost.
- b. Unit has not completed 2 Year – should have annual turnover at least 10% of estimated cost/Quoted Quantity Cost.
- c. Unit has not completed 3 Year - should have Average Annual Turnover of last 2 years equal to 10% of estimated cost / Quoted Quantity Cost

1. Net worth Requirement:

For General Bidder/MSE of Jharkhand/NEW MSEs: Bidder should have Positive Net Worth as on 31.03.2025 on the basis of audited annual accounts.

Net worth certificate should be issued by CA with UDIN no. as per the Performa given at **Annexure-6**

(III) Technical Requirement:

Solar Photo Voltaic Mini/Micro Grid Grouped into 4 parts according to Capacity of plant. **Bidder can participate only in one Category from Group A ,B C & D (Solar Photo voltaic Mini/Micro Grid with Battery System i.e Group A,B,C,D)**

NOTE-**Participating in more than one Group from Group A,B,C & D will lead to disqualification of the bidder for evaluation.

Category No.	Group
1	Group "A" 1 to 10 kWp (Solar Photo voltaic Mini/Micro Grid With Battery System)
2	Group "B" 11 to 50 kWp (Solar Photo voltaic Mini/Micro Grid With Battery System)
3	Group "C" 51 to 100 kWp (Solar Photo voltaic Mini/Micro Grid With Battery System)
4	Group "D" above 100 kWp (Solar Photo voltaic Mini/Micro Grid With Battery System)

Table 1

Require Technical Experience criteria: Copy of work order along with work completion certificate from any Government PSU/SNA as per the given table below			
Sr. No.	Group	Require Qualification for General Bidder	Require Qualification for MSEs Bidder
1	Group "A" 1 to 10 kWp With Battery System)	10 kWp of one system or 1kWp of 3 Nos system	10 kWp of one system or 1kWp of 2 Nos system
2	Group "B" 11 TO 50 kWp With Battery System)	50 kWp of one system or 10kWp of 3 Nos system	50 kWp of one system or 10kWp of 2 Nos system
3	Group "C" 51 to 100 kWp with Battery system	100 kWp of one system or 50 kWp of 3 Nos system	100 kWp of one system or 50kWp of 2 Nos system
4	Group "D" Above 100 kWp (With Battery System)	Above 100 kWp of one system or 100kWp of 3 Nos system	Above 100 kWp of one system or 100kWp of 2 Nos system

For General Bidder: Experience of having successfully completed similar works in any SNA / Govt. Organization / PSU during last 7 years ending last day of month previous to the one in which applications are invited should be either of the following: -

- I. Three similar work equal to the maximum capacity under the category one below the category applied for.
e.g. If bidder is applying for group "B" then he must have three complete sites of 10 kW each.

or

- II. One similar site work capacity equal to the applied group.
e.g., If bidder is applying for group "B" then he must have one complete site of 50 kW.

For MSEs of Jharkhand: Experience of having successfully completed similar works in any SNA / Govt. Organization / PSU during last 7 years ending last day of month previous to the one in which applications are invited should be either of the following: -

- I. Two similar work equal to the maximum capacity under the category one below the category applied for.
e.g. If bidder is applying for group "B" then he must have two complete sites of 10 kW each.

or

- II. One similar site work capacity equal to the applied category.
e.g., If bidder is applying for group "B" then he must have one complete site of 50 kW.

For New MSEs of Jharkhand: New-MSME of Jharkhand shall be exempted from the Experience requirement. The copy of work order and certificate indicating its successful execution should be enclosed.

Note: Bidder shall participate only in one Category/Group from Group A,B,C & D mentioned above, in BOQ otherwise participating in more than one category/Group from Group A,B,C & D bid will lead to rejection of the bid.

Definition of Similar Work: - Bidder should have experience of Design, Engineering, Supply, Installation, and Testing & Commissioning of **Solar Power Plant equivalent** to minimum quoted Quantity. Each Work Order along with successful work completion certificate will be considered as one "Similar completed work"

Valid Test Report from any test center approved/recognized by MNRE/test labs accredited by NABL and approved by BIS as per Lab Policy for Testing, Standardization and Certification for Renewable Energy Sector (Circular No. 3-2/2015-16(R&D) dated 07/12/2017.

Sr. No.	Components	Standards
1	Solar Module	Should conform to the latest BIS/ International standards /IEC61215edition II / BIS 14286, IEC 61730 part I & II, IEC 62804 or
2	PCU	As per latest IEC/ equivalent BIS standard for efficiency measurements and environmental tests as per standard codes IEC 61683/IS 61683 and IEC 60068-2 (1,2,14,30)/ Equivalent BIS Std., IEC60068-2 (1, 2, 14, 30)/ Equivalent BIS std., IEC 62109-1 & 2/ Equivalent BIS std
3	Battery	Should conform to the latest BIS/ International standards /IS 15549,:2015,IS16047 equivalent latest BIS , IEC 61427 ,16046 or relevant latest IS specifications as per MNRE requirements.

The Bidder should confirm that they have the resources and capability to supply the offered quantity within the scheduled period in the form of an undertaking.

****Note: All the above test reports are mandatory for being technically eligible.**

(IV) Procedure for Award of Work:

- i. The lowest rate, i.e., L1 received would be the appropriate rate for awarding the work in each category.
- ii. JREDA will award the Contract to the Bidder whose Bid has been found technically and financially successful by JREDA Purchase committee and who has been empaneled under different category.
- iii. JREDA shall empanel all the bidders on acceptance of lowest (L1) rate in each category.
- iv. To encourage the New MSMEs of Jharkhand, JREDA may consider for awarding the work on acceptance of L-1 rate.
- v. Allocation of the quantity to MSEs registered in Jharkhand will be made as per the provisions made in Jharkhand Procurement Policy.
- vi. If quantity/capacity is left unallocated in any category, JREDA reserves the right to reallocate the left-over quantity to other categories.
- vii. Agency who apply for only one Category, However JREDA reserve the right to may empanel work of one category to other category on subjected to acceptance of L1 Rate.
- viii. JREDA will allocate initial capacities/quantities to empaneled bidders based on their bid capacities and available capacities. If Bidder is a working agency of JREDA then allocation of capacities/quantities will be done based on the bid capacities and their past performances in JREDA like timely completion of allotted work and timely submission of CMC report and performance certificate marks etc. JREDA will review the progress of each agency on a monthly basis and a performance appraisal will be done after completion of three months. On the basis of performance appraisal quantities allocated to agencies will be revised.

SECTION-4

Instruction to Bidder

NIB No: 03/JREDA/OFFGRID/RC/26-27

Table of Clauses

Clause A. General		Clause D. Submission of Bids	
1	Scope of Bid	17	Deadline for Submission of Bids
2	Source of Funds		
3	Eligible Bidders	E.	Bid Opening
4	Qualification of the Bidder	18	Bid Opening
5	One Bid per Bidder	19	Process to be Confidential
6	Cost of Bidding	20	Clarification of Bids and Contracting the JREDA
		21	Examination of bids and Determination of Responsiveness
B.	Bidding Documents and Evaluation		
		22	Correction of Errors
7	Content of Bidding Documents	23	Evaluation and Comparison of Bids
8	Clarification of Bidding Documents	24	Price Preference
9	Amendment of Bidding Documents	F.	Award of Contract
C.	Preparation of Bids	25	Award Criteria
10	Language of Bid	26	JREDA Right to Accept any Bid And to reject any or all Bids
11	Documents Comprising the Bid	27	Notification of Award
12	Bid Prices	28	Performance Security
13	Currencies of Bid	29	Corrupt or Fraudulent Practices
14	Bid Validity		
15	Earnest Money		
16	Sealing and Marking of Bids		

Instructions to Bidders (ITB)

A. General

1. Scope of Bid

- 1.1. The JREDA invites bids for the work as described in these documents and referred to as "the work". The name and identification number of the works is provided in the Notice Inviting Bid.
- 1.2. The successful Bidder will be expected to complete the Works by the Intended Completion time specified in the General Conditions of Contract.
- 1.3. Throughout these documents, the terms "bid" and "tender" and their derivatives (bidder/ tenderer, bid/ tender, bidding/ tendering) are synonymous.
- 1.4. Electrification of each village will be considered as single project

2. Source of Funds

- 2.1. The JREDA has decided to undertake the works of "Request for Proposal (RFP) for Design, Engineering, Supply, Installation Testing & Commissioning of Solar Photo Voltaic Mini/Micro Grid with distribution network including control room & Connection to households along with 5 years Operation & Comprehensive Maintenance Contract (CMC) on Turnkey basis in different Villages anywhere in Jharkhand through funds from the GOJ to be implemented through JREDA.

3. Eligible Bidders

- 3.1 This Invitation for Bids is open to all bidders as defined in the Notice Inviting Bid.
- 3.2 Bidders shall not be under a declaration of ineligibility for corrupt and fraudulent practices /debarred/blacklisted by the Central Government, the State Government or any public undertaking, autonomous body, authority by whatever name called under the works.

4. Qualification of the Bidder

- 4.1 All bidders shall provide in Section 3, Forms of Bid and Qualification information, a preliminary description of the proposed work method and schedule, including drawings and charts, as necessary.
- 4.2 All bidders shall include the following information and documents with their bids in Section 3, Qualification Information unless otherwise stated in the Notice Inviting Bid/ITB.
- 4.3 Copies of original documents defining the constitution or legal status, place of registration, and principal place of business.
- 4.4 Copy of written power of attorney of the signatory of the Bid to commit the Bidder.
- 4.5 Experience in works of a similar nature and size for each of the last seven years, and details of works in progress or contractually committed with certificates from the concerned officer or competent authority.
- 4.6 Reports on the financial standing of the Bidder, such as profit and loss statements and auditor's reports for the last three FY years.

- 4.7 Bidder shall submit all the information required to be provided as per Annexures.
- 4.8 Even though the bidders meet the qualifying criteria of Section-3, they are subject to be disqualified if they have:
- i. made misleading or false representations in the forms, statements, affidavits and attachments submitted in proof of the qualification requirements; and/or
 - ii. record of poor performance such as abandoning the works, not properly completing the contract, inordinate delays in completion, litigation history, or financial failures
 - iii. Participated in the previous bidding for the same work and had quoted unreasonably high or low bid prices and could not furnish rational justification for it to JREDA.

5. One Bid per Bidder

- 5.1 Each Bidder shall submit only one Bid for one work. A Bidder who submits more than one Bid will cause the proposals with the Bidder's participation to be disqualified.

6. Cost of Bidding

- 6.1 The Bidder shall bear all costs associated with the preparation and submission of his Bid, and the JREDA will, in no case, be responsible or liable for those costs.

B. Bidding Documents

7. Content of Bidding Documents

- 7.1 The set of bidding documents comprises the documents listed below and addenda issued in accordance with Clause 10 of ITB.
- a. Notice Inviting Tender
 - b. Instructions to Bidders
 - c. Qualification Information
 - d. Conditions of Contract
 - e. Bill of Quantities
 - f. Form of Bid
 - g. Form of Bank Guarantee.
- 7.2 The bidder is expected to examine carefully all instructions, conditions of contract, contract data, forms, terms and specifications, bill of quantities, forms in the Bid Document. Failure to comply with the requirements of Bid Documents shall be at the bidder's own risk. Pursuant to clause 21 hereof, bids, which are not substantially responsive to the requirements of the Bid Documents, shall be rejected.

8. Clarification of Bidding Documents and Pre-Bid Meeting

- 8.1 A prospective Bidder requiring any clarification of the bidding documents may notify the JREDA in writing at the JREDA's address indicated in the Notice Inviting Tenders.
- 8.2 Pre-bid meeting will be held in the Conference Hall of JREDA. The bidder or his authorized representative may attend the meeting.
- 8.3 The purpose of such a meeting will be to clarify issues and to answer questions on any matter that may be raised at that stage.
- 8.4 The bidder is requested to submit any questions in writing so as to reach the JREDA not later than two days before the meeting.
- 8.5 Any modifications of the bidding documents listed in Clause 8.1 of ITB, which may become necessary as a result of the pre-bid meeting shall be made by the JREDA exclusively through the issue a Corrigendum/Addendum.

8.6 Non-attendance at the pre-bid meeting will not be a cause for disqualification of a bidder.

9. Amendment of Bidding Documents

9.1 Before the deadline for submission of bids, JREDA may modify the bidding documents by issuing corrigendum/addendum.

9.2 To give prospective bidders reasonable time in which to take a corrigendum/addendum into account in preparing their bids, the JREDA shall extend, if necessary, the deadline for submission of bids, in accordance with Clause 17.2 of ITB.

C. Preparation of Bids

10. Language of Bid

10.1 All documents relating to the Bid shall be in the English language specified in the Notice Inviting Bid.

11. Documents Comprising the Bid

11.1 Technical Bid – (Fee/Pre-Qualification/Technical Cover)

i. EMD & Tender Fee online mode

ii. Only electronic receipt of Cost of Tender and Earnest Money Deposit (Bid Security) will be acceptable as per provisions of Standard Operating Procedure (SOP). Issued by Information Technology & e-Governance Department, Government of Jharkhand Vide Order Memo No. 120, Dt. 03.10.23 of Secretary, Information Technology & e-Governance Department, Government of Jharkhand.

iii. Technical Details & Declaration

a. Proposed work program me (work method, time schedule and financial flow), description, and charts as necessary (Duly to be signed digitally) to comply with the requirement of the Bidding Document.

b. Scanned copy of an Affidavit by the Bidder that he/she has accepted the S.B.D.

iv. Valid test Report from any test center approved/recognized by MNRE/test labs accredited by NABL as per lab policy of the offered system

v. Technical Details of documents

Scanned copies/Prescribed Formats of Documents to be attached in "My Document" in .pdf format file duly digitally signed by the bidder as described in Section 2 clause 11

11.2 Financial Bid – (Finance Cover)

a. Duly Quoted & digitally signed Bill of Quantity (BoQ) in the file supplied by JREDA in .xls/.pdf format shall be uploaded.

NOTE: - All the documents should be digitally signed.

11.3 The following documents, which are not submitted with the bid, will be deemed to be part of the bid.

Section Particulars

a. Notice inviting Tender

b. Instruction to the bidders

c. Conditions of Contract

d. Contract Data

12. Bid Prices

12.1 The Contract shall be for the whole Works, as described in Clause 1.1 of ITB.

12.2 The Bidder shall adopt the Item Rate Method as specified in the Notice Inviting Bid only the same option is allowed to all the Bidders.

- 12.3 All duties, taxes, royalties and other levies payable by the Contractor under the Contract, or for any other cause, shall be included in the rates, prices, and total Bid price submitted by the Bidder.
- 12.4 The rates and prices quoted by the Bidder shall be fixed for the duration of the Contract and shall not be subject to adjustment.
- 12.5 **Price bids submitted by New MSEs shall not be considered.** However, to complete the tender process New MSEs have to submit price bids. They have to accept the L1 rate derived in tender for award of work.
- 12.6 **Bidder shall quote the price bid to complete the bid process and the bidder will quote rate in only in one category from Group A, B C & D in BOQ otherwise participating in more than one category will lead to disqualification of the bidder for evaluation.**
- 12.7 **The bidder should declare the quoted quantity in the prescribed Annexure-17.**
- 12.8 **Price bid shall be opened and evaluated for the bids who shall quote the minimum requirement of quoted quantity as indicated below. Bidder quoted lesser than the minimum quoted quantity, will be disqualified.**

S.N.	Group	Minimum requirement of Quoted Quantity for considering opening & evaluation of Price Bid
1	Group "A" 1 to 10 kWp (Solar Photo voltaic Mini/Micro Grid with Battery System)	100 kWp
2	Group "B" 11 to 50 kWp (Solar Photo voltaic Mini/Micro Grid with Battery System)	250 kWp
3	Group "C" 51 to 100 kWp (Solar Photo voltaic Mini/Micro Grid with Battery System)	500kWp
4	Group "D" above 100 kWp (Solar Photo voltaic Mini/Micro Grid with Battery System)	500 kWp

13. Currencies of Bid

- 13.1 The unit rates and the prices shall be quoted by the bidder entirely in Indian Rupees (INR).

14. Bid Validity

- 14.1 Bids shall remain valid for a period of 180 (One Hundred Eighty) days after the deadline date for bid submission specified in Clause 19 of ITB. A bid valid for a shorter period shall be rejected by the JREDA as non-responsive.

15. Earnest Money

- 15.1 The Bidder shall furnish, as part of the Bid, Earnest Money through online mode, in the amount specified in the Notice Inviting Bid.
- 15.2 Only electronic receipt of Cost of Tender and Earnest Money Deposit (Bid Security) will be acceptable as per provisions of Standard Operating Procedure (SOP).
- 15.3 The Earnest Money of unsuccessful bidders will be returned as per Standard Operating

Procedure (SOP). Issued by Information Technology & e- Governance Department, Government of Jharkhand Vide Order Memo No. 120, Dt. 03.10.23 of Secretary, Information Technology & e-Governance Department, Government of Jharkhand. (Copy Attached

- 15.4 The Earnest Money of the successful Bidder will be discharged when the Bidder has signed the Agreement and furnished the required Security Deposit.
- 15.5 The Earnest Money may be forfeited:
- a. if the Bidder withdraws the Bid after bid opening (technical bid) during the period of Bid validity;
 - b. in the case of a successful Bidder, if the Bidder fails within the specified time limit to
 - i. sign the Agreement; and/or
 - ii. Furnish the required Security Deposit.

16. Sealing and Marking of Bids

- 16.1 The Bidder shall place the file marked "Technical Bid". The file will have markings as follows:

Technical Bid: To be opened on (date and time of Technical Bid opening as per clause 18.1 of ITB.)

The Technical bid file shall only contain Only electronic receipt of Cost of Tender and Earnest Money Deposit (Bid Security) will be acceptable as per provisions of Standard Operating Procedure (SOP). Issued by Information Technology & e- Governance Department, Government of Jharkhand Vide Order Memo No. 120, Dt. 03.10.23 of Secretary, Information Technology & e-Governance Department, Government of Jharkhand.

- 16.2 The file containing the Technical Bid shall
- a) Be addressed to the JREDA at the address provided in the Notice Inviting Bid
 - b) Bear the name and identification number of the Contract as defined in clause 1.1 of ITB; and
 - c) Provide a warning not to open before the specified time and date for Bid opening as defined in clause 18.1 of ITB.

D. Submission of Bids

17. Deadline for Submission of Bids

- 17.1 Complete Bids (including Technical and Financial) must be received by the JREDA at the address specified in the Notice Inviting Bid not later than the date and time indicated in the Notice Inviting Bid.
- 17.2 The JREDA may extend the deadline for submission of bids by issuing an amendment in accordance with Clause 8.3 of ITB, in which case all rights and obligations of the JREDA and the bidders previously subject to the original deadline will then be subject to the new deadline.

18. Bid Opening

- 18.1 The JREDA will open the bids received (except those received late). In the event of the specified date for the submission of bids being declared a holiday for JREDA, the Bids will be opened at the appointed time and location on the next working day.
- 18.2 The files containing the technical bid shall be opened. The document marked "cost of bidding document" will be opened first and if the cost of the bidding documents is not there, or incomplete, the remaining bid documents will not be opened, and bid will be rejected.

- 18.3 In all other cases, the amount of Earnest Money, forms and validity shall be announced. Thereafter, the bidders' names and such other details as the JREDA may consider appropriate, will be announced by the JREDA at the opening.
- 18.4 The JREDA will prepare minutes of the Bid opening, including the information disclosed to those present at the time of Bid Opening.
- 18.5 Evaluation of the technical bids with respect to bid security, qualification information and other information shall be carried out as per e-procurement guideline.
- 18.6 The JREDA shall inform, by email, the bidders, whose technical bids are found responsive, date, time and place of opening as stated in the Notice Inviting Bid. In the event of the specified date being declared a holiday for the JREDA, the bids will be opened at the appointed time and location on the next working day through they or their representative, may attend the meeting of opening of financial bids.
- 18.7 At the time of the opening of the 'Financial Bid', the names of the bidders whose bids were found responsive in accordance with clause 18.5 of ITB will be announced. The financial bids of only these bidders will be opened. The remaining bids will be returned unopened to the bidders. The responsive bidders' names, the Bid prices, the total amount of each bid, and such other details as the JREDA may consider appropriate will be announced by the JREDA at the time of bid opening. Any Bid price which is not read out and recorded, will not be taken into account in Bid Evaluation
- 18.8 The JREDA shall prepare the minutes of the opening of the Financial Bids
- 18.9 If the Bidder submitted Price bid in bid document than will lead to rejection of the bid.

19. Process to be Confidential

- 19.1 Information relating to the examination, clarification, evaluation, and comparison of bids and recommendations for the award of a contract shall not be disclosed to bidders or any other persons not officially concerned with such process until the award to the successful Bidder has been announced. Any attempt by a Bidder to influence the JREDA's processing of bids or award decisions may result in the rejection of his Bid.

20. Clarification of Bids and Contacting the JREDA

- 20.1 No Bidder shall contact the JREDA on any matter relating to its bid from the time of the bid opening to the time the contract is awarded.
- 20.2 Any attempt by the bidder to influence the JREDA's bid evaluation, by any means, bid evaluation, bid comparison or contract award decision may result in the rejection of his bid.

21. Examination of Bids and Determination of Responsiveness

- 21.1 During the detailed evaluation of "Technical Bids", the JREDA will determine whether each Bid
- (a) Meets the eligibility criteria defined in section 3.
 - (b) Has been properly signed;
 - (c) Is accompanied by the required securities; and
 - (d) is substantially responsive to the requirements of the bidding documents. During the detailed evaluation of the "Financial Bids", the responsiveness of the bids will be further determined with respect to the remaining bid conditions, i.e. Backend, Integration & Databases Services, Report and feedback services.
- 21.2 The "Financial bids" of only those bidders (for general bidders only) shall be opened, who qualify all the criteria of "Minimum Eligibility Conditions".

- 21.3 A substantially responsive "Financial Bid" is one, which conforms to all the terms, conditions, and specifications of the bidding documents, without deviation as per requirement of NIB. A deviation or reservation is one (a) which affects in any substantial way the scope, quality, or performance of the Works; (b) which limits in any substantial way, inconsistent with the bidding documents, the JREDA's rights or the Bidder's obligations under the Contract; or (c) whose rectification would affect unfairly the competitive position of other bidders presenting substantially responsive bids.
- 21.4 If a "Financial Bid" is not substantially responsive, it will be rejected by the JREDA, and may not subsequently be made responsive by correction or withdrawal of the nonconforming deviation or reservation.

22. Corrections of Errors

- 22.1 Bids determined to be substantially responsive, will be checked by the JREDA for any arithmetic errors. Errors will be corrected by the JREDA as follows:
- a. where there is a discrepancy between the rates in figures and in words, the rate in words will govern; and
 - b. Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by the quantity, the unit rate as quoted will govern.
- 22.2 The amount stated in the Bid will be adjusted by the JREDA in accordance with the above procedure for the correction of errors and shall be considered as binding upon the Bidder. If the Bidder does not accept the corrected amount, the Bid will be rejected, and the Earnest money shall be forfeited in accordance with tender documents.

23. Evaluation and Comparison of Bids

- 23.1 The JREDA will evaluate and compare only the bids determined to be substantially responsive in accordance with tender documents.
- 23.2 In evaluating the bids, the JREDA will determine for each Bid the evaluated Bid price by adjusting the Bid price by making correction, if any, for errors pursuant to Clause 22 of ITB.
- 23.3 If the Bid of the successful Bidder is seriously unbalanced in relation to the Engineer's estimate of the cost of work to be performed under the contract, the JREDA may require the Bidder to produce detailed price analysis for any or all items of the Bill of Quantities, to demonstrate the internal consistency of those prices with the construction methods and schedule proposed. After evaluation of the price analyses, the JREDA may require that the amount of the performance security set forth in Clause 28 of ITB be increased at the expense of the successful Bidder to a level sufficient to protect the JREDA against financial loss in the event of default of the successful Bidder under the Contract. The amount of the increased performance security shall be decided at the sole discretion of the Employer, which shall be final, binding and conclusive on the bidder.
- 23.4 After its evaluation, the JREDA may require that the amount of the performance security set forth in Clause 28 be increased at the expense of the successful Bidder to a level

sufficient to protect the JREDA against financial loss in the event of default of the successful Bidder under the Contract. The amount of the increased performance security shall be decided at the sole discretion of the JREDA, which shall be final, binding and conclusive on the bidder.

23.5 Bid Evaluation criteria: -

S.N.	Applied Category by Bidder as per Annex 18	Bid Document	Remarks
1	General	Document found 'OK' for General, MSEs and/or NEW MSEs	Shall be Consider for General category
2	General	Document found 'OK' for MSEs and/or NEW MSEs	Shall not be consider for any category. The Bid shall be rejected
3	MSEs	Document found 'OK' for General, MSEs and/or NEW MSEs	Shall be Consider only for MSEs category
4	MSEs	Document found OK for General or NEW MSEs	Shall not be consider for any category. The Bid shall be rejected
5	NEW MSEs	Document found OK for General & NEW MSEs	Shall be Consider only for NEW MSEs category
6	NEW MSEs	Document found 'OK' for General and MSEs	Shall not be consider for any category. The Bid shall be rejected

24. Price Preference

24.1 There will be no price preference to any bidder.

E. Award of Contract

25. Award Criteria

25.1 JREDA will award the Contract to the Bidder whose Bid has been successful and who has been empaneled.

Empanelment Procedure

25.2 The lowest rate i.e., L1 received would be the appropriate rate for awarding the work in each category.

25.3 JREDA shall empanel all the bidders on acceptance of lowest (L1) rate in each category.

25.4 Allocation of the quantity to MSEs registered in Jharkhand will be made as per the provisions made in Jharkhand Procurement Policy 2019.

25.5 If quantity/capacity is left unallocated in any category/Group, JREDA reserves the right to reallocate the left-over quantity to other categories/Group.

25.6 JREDA will allocate initial capacities/quantities to empaneled bidders based on their bid capacities and available capacities. If Bidder is a working agency of JREDA then allocation of capacities/quantities will be done based on the bid capacities and their past performances in JREDA like timely completion of allotted work and timely submission of CMC report and performance certificate marks etc. JREDA will review the progress of each agency on monthly basis and a performance appraisal will be done after completion of three months. On the basis performance appraisal quantities allocated to agencies will be revised

26. JREDA's Right to accept any Bid and to reject any or all Bids

- 26.1 Notwithstanding Clause 25 above, the JREDA reserves the right to accept or reject any Bid, and to cancel the bidding process and reject all bids, at any time prior to the award of Contract, without thereby incurring any liability to the affected Bidder or bidders or any obligation to inform the affected Bidder or bidders of the grounds for the JREDA's action without any reason.

27. Notification of Award and Signing of Agreement

- 27.1 The bidder whose Bid has been accepted will be notified of the award by the JREDA prior to expiration of the Bid validity period by cable, email, telex or facsimile confirmed by registered letter. This letter (hereinafter and in the Part I - General Conditions of Contract called the "Letter of Acceptance") will state the sum that the JREDA will pay to the Contractor in consideration of the execution and completion of the Works (hereinafter and in the Contract called the "Contract Price").
- 27.2 The notification of award will constitute the formation of the Contract, subject only to the furnishing of a performance security in accordance with the provisions of Clause 30.
- 27.3 The Agreement will incorporate all agreements between the JREDA and the successful Bidder. It will be signed by the JREDA and the successful Bidder after the performance security is furnished.
- 27.4 Upon the furnishing by the successful Bidder of the Performance Security, the JREDA will promptly notify the other Bidders that their Bids have been unsuccessful.

28. Security Deposit:

- 28.1 Successful General bidder shall submit a **security deposit @10%** of the allotted work order value in the form of Demand Draft/Bank Guarantee/FDR/TDR valid for one year on or before 15 days from issuing work order. If Bank Guarantee/DD/FDR/TDR will not be submitted within stipulated period from the date of issue of work order, then JREDA shall cancel the work order.
- 28.2 Successful MSE bidders shall be required to deposit **only 1%** of security deposit (MSE Bidder) i.e. @1% of the allotted work order value in the form of Bank Guarantee/DD/FDR/TDR valid for one year as per Jharkhand Procurement Policy.
- 28.3 The Security Deposit shall be refunded / released to the bidder after successful completion of work and submission of performance guarantee.
- 28.4 The Security Deposit will have to be maintained by the bidder with JREDA till the satisfactory completion of the work. If the work extends beyond the expiry date of Bank Guarantee, bidders shall submit fresh or extend the period of validity of Bank Guarantee as per the direction of JREDA, otherwise JREDA may terminate the work order and blacklist the contractor.

29. Performance Guarantee:

- 29.1 Successful General bidder shall submit a performance guarantee **@5%** of the allotted work order value in the form of Demand Draft/Bank Guarantee/FDR/TDR valid for five years on or before release of Payment against Installation.
- 29.2 Successful MSE bidders shall submit a Performance Guarantee **@0.5%** of the allotted work order value in the form of bank guarantee/DD/FDR/TDR before release of payment against Installation.

- 29.3 The Performance Guarantee will have to be maintained by the bidder with JREDA till the completion of warrantee period.
- 29.4 The Security Deposit/Performance Guarantee shall be submitted in the form of bank guarantee/FDR/TDR/DD in favour of "Director, JREDA" payable at Ranchi from any Indian Nationalized bank/Scheduled bank.
- 29.5 Non submission of Security Deposit/Performance Guarantee within the time frame, shall lead to forfeiture of EMD and cancellation of work order.
- 29.6 If Bidder/MSE unit fails to carry out the work allotted to him as per the provisions of the tender documents, then such Bidder/MSE unit may be black listed for future awards of work.
- 29.7 Bank Guarantees must be confirmed through SFMS (Structured Financial Messaging System) mode. Physical mode, electronic mode i.e. e-mail.

30. Liquidated damages for delay in completion of Work:

If the Successful Bidder fails to complete the Work within the period specified in the Agreement or any extension granted thereto under force majeure conditions, JREDA will recover from the Successful Bidder as penalty @ 0.5% at the contract price for each week of delay. The total penalty shall not exceed 10% (ten percent) of the contract price. Beyond 10 weeks of delay, JREDA may:

- a) Allow Successful Bidder to continue Work; OR
- b) JREDA may terminate the Contract with Successful Bidder and get Work completed by other party at risk and cost of Successful Bidder.

In either of the cases above, JREDA would recover the loss of subsidy from the Successful Bidder. This recovery shall be in addition to penalty for delay for 10 weeks.

31. Five Years Comprehensive Maintenance Contract (CMC)

1. Solar Mini Grid SPV Power Plant contract price includes the provision of 5 years mandatory Comprehensive Maintenance Contract (CMC). To ensure long term sustainability of the system, the bidder must provide his representatives name, full address, mobile number and photographs to JREDA with one hard copy as well as the names and contact details of all technicians must also be provided. Failure to do shall invite penalty and action.
2. The Comprehensive Maintenance Contract shall include servicing & replacement guarantee for parts and components (such as battery, PCU, electronics, Inverter, PV modules and other hardware etc.) of solar Off-Grid SPV Power Plant for five years from the date of installation. PV modules shall be warranted for 25 years. Battery should be warranted for a minimum life of 5 years. The date of CMC maintenance period shall begin on the date of actual commissioning of solar Off-Grid SPV Power Plant & Solar Home light system. It is mandatory for the contractor to carry out CMC regularly and submit report to JREDA timely. Failure to submit Quarterly CMC reports and monthly generation data of plant timely shall invite penalty and action.
3. For any issue related to operation & maintenance, a contact number shall be made available to the concerned departments to resolve immediately, if the bidder do not attempt the rectification of any such defect within three days of communication of such complaint to the bidders, the bidder will be liable for a penalty of @0.5% at the contract price for each week of delay. The total penalty shall not exceed 10% of the contract price. Further if the outage of the plant is more than 30 days continuously, then the penalty 50% amount equal to PBG shall be recovered by JREDA either by Deduction from the CMC bill or the bidder shall pay to JREDA as penalty through DD/ and if the outage is exceeding more than 60 days than complete PBG amount shall be encashed by JREDA. This will be applicable till 5 years of O&M as per the scope of the RFP. Bidder shall submit Quarterly CMC report as per the **Annexure 13(Solar Mini/Micro Grid)** and bidder shall submit **Monthly generation data (Annexure 19)** (for Solar Mini/micro grid plant) of month within 7 working days of subsequent month. Failure to

submit Quarterly CMC reports and Monthly Generation Report timely shall invite penalty and action.

- The Contractor should have sufficient numbers of skilled staff for proper maintenance of solar off-grid power plant. The contractor has to make suitable arrangement for running, operation and maintenance of SPV Power Plant by deputing electrician and other skilled persons required in the plant 24 x 7 so that SPV off grid Power Plant will be functional every day. It is mandatory for the contractor to carry out CMC regularly for Solar Mini grid system and submit report including maintenance schedule to JREDA. Failure to submit quarterly CMC reports & monthly Generation Report (Solar Mini/Micro grid Plant) timely shall invite penalty and action.

32. Insurance:

- The supplier shall arrange for transit and erection insurance of the materials & equipment's for supply & installation of Solar System including distribution network along with Insurance of each installed Solar mini/micro grid plant as per DI.
- The Supplier shall arrange for insurance against any type of theft/damage defect of the complaint/sub-complaints for the complete comprehensive maintenance contract (CMC) period.

33. Corrupt or Fraudulent Practices

The JREDA requires the bidders/Contractors to strictly observe the laws against fraud and corruption in force in India, namely, Prevention of Corruption Act, 1988.

34. Estimated rate of different category

JREDA invited experienced manufacturer/Agency for getting Benchmark cost vide PR No 378266 Enery (26-27) for the work "Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand". Minimum rate identified is considered for estimated rate. Details of rate for different category is mentioned as below: -

Category No.	Group	Estimated rate per kWp (Excluding GST)
1	Group "A" 1 to 10 kWp (Solar Photo voltaic Mini/Micro Grid with Battery System)	258500.00
2	Group "B" 11 to 50 kWp (Solar Photo voltaic Mini/Micro Grid with Battery System)	207900.00
3	Group "C" 51 to 100 kWp (Solar Photo voltaic Mini/Micro Grid with Battery System)	216427.00
4	Group "D" 51 to 100 kWp (Solar Photo voltaic Mini/Micro Grid with Battery System)	227608.00

Section-5

General Terms & Conditions

NIB No: 03/JREDA/OFFGRID/RC/26-27

1. Introduction:

The instruction/information contained in the bid documents are for guidance and compliance of the intending bidder. Bidders are advised to obtain clarification from JREDA, if any, prior to submission of their bid, failing which it will be deemed that the stipulation made in the bid documents have been read, understood and are acceptable to the bidder.

Bidder shall bear all costs associated with the preparation and submission of the bid, journeys undertaken by them and subsequent bidding process till the award of the order to successful bidder and the JREDA shall in no case, shall be responsible or liable for these costs, regardless of the conduct or outcome of the bidding process.

2. Scope of work:

A. For Solar Mini Grid System

Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand

- a) Design, Construction of suitable control room of Solar Photovoltaic Power Plants (Mini/Micro Off grid) for battery Bank, Power Conditioning Unit (PCU) & Control Panels required for defined capacity of SPV Power Plant in different villages anywhere in the state of Jharkhand and Operation & maintenance of system for five years as amended/ replaced/ Sub-assumed as mentioned in the tender document and clause 1.24 (PDN) of section 6.
- b) The work for "**Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand**" complete set in all respects along with one set of operational instruction cum maintenance manual (both English and Hindi) for each set and delivery on destination/site (door delivery) basis across the State of Jharkhand as per the direction of JREDA
- c) Preparation of Pre-Feasibility Report (PFR) /site survey report (Annexure20) of the proposed sites of Solar Mini/Micro grid system which should include recommendation of village level Committee members including Mukhiya. In case village/tola is found to be electrified through conventional grid than you have to submit request for site change. Apart from this Bidder shall submit Declaration as per the Annexure 19
- d) **Chain-Link Fencing:** The Contractor shall provide chain-link fencing of the entire solar-off grid Plant boundary for plant sites. Details are mention in accordance with the provision of clause 1.24 of Section 6
- e) Execution of the work shall be carried out in an approved manner as per the technical specification of NIB, in case of any dispute relevant latest MNRE/BIS/ISI specification shall be followed.
- f) Providing Prompt Service Facilities to customers/ beneficiaries. The Contractor shall maintain sufficient tools and spares near the installation sites for the quick repair and maintenance.
- g) Training of beneficiary, on the various aspects of design and maintenance of the offered system after commissioning of the system.

h) Contractor has to depute at least two (2) Skill manpower for 24*7 Solar Plant monitoring.

NOTE** Manpower must be on that village only.

- i) Unconditional onsite warrantee for manufacturing defects for Five years faultless operation, assure required inventory for maintenance.
- j) Providing Prompt Service Facilities to customers/ beneficiaries. The Contractor shall maintain sufficient tools and spares near the installation sites for the quick repair and maintenance.
- k) Risk liability of all personnel associated with implementation and realization of the project.
- l) Bidder shall furnish all necessary information to village energy committee for Solar mini grid plant, Do & Don'ts etc. so as to avoid further misunderstandings and disputes.
- m) The Contractor shall provide Energy Meter for measurement of electricity consumption of the solar-off grid Plant.

3. Bid documents:

Tender documents shall comprise of all the documents mentioned in this Bid. In addition to these any other documents/amendments/revisions or instructions issued by JREDA from time to time to bidders till due date of opening of the offers, shall also be deemed to be integral part of the bid document.

4. Price:

The bidder shall quote his price as per schedule of items of work. The contract price rates shall be firm and binding and shall not be subject to any variation except for statutory variation of taxes and duties during the contractual completion period. The price shall be Excluding GST and inclusive of all taxes, duties and levies and 5 years CMC etc. as on the opening date of tender. **as on the opening date of tender.** The price shall also include designing, manufacturing, inspection, supply, transport, insurance, handling etc. All applicable charges for taking necessary clearance such as commercial tax, road permit etc. wherever required are also deemed to be included in the contract price.

5. Dispatch Instructions:

All items/equipment's shall be subject to **Pre-Dispatch Inspection (PDI)** by JREDA or its authorized representatives at the manufacturing site before their dispatch. The sample size for **PDI** shall be in accordance with BIS norms or minimum @ 2% of the quantity offered, which will be randomly selected. However, representative of JREDA will have right to demand bigger sample size, if required. The manufacturing site must have sufficient testing facilities conforming to NABL facility. The manufacturer will submit test report with regard conformity to technical specifications for the items to be dispatched to work site of JREDA. However, equipment's will be dispatched from the manufacturing site only after the receipt of "Dispatch Clearance" from JREDA after acceptance of test report.

- Randomly selected Sample/s from each lot offered for PDI, may be sent to MNRE approved or NABL accredited lab for verification of Specifications and Performance of the System. The cost of such tests shall be borne by JREDA.
- No consignment shall be dispatched without the receipt of dispatch clearance from JREDA. No PDI shall be done at any site other than the concerned manufacturing site. Successful bidders have to arrange necessary equipment's conforming to NABL facility for testing the materials to

be supplied during the pre-dispatch inspection by JREDA at their manufacturer’s unit. Failure to fulfill the PDI conditions shall lead to cancellation of work order and forfeiture of security deposit.

- The items which are being procured through this bid have to be distributed/installed on the basis of demand to be received by JREDA. Therefore, JREDA does not take responsibility that it will procure 100% quantity as has been indicated in the bid. Further, as JREDA will receive the demand and fund, the supply order shall be placed to the successful bidder for execution in due time.
- After finalization of the tender JREDA authority will take decision for issuing work order for the work under scope to the successful bidder; and thereafter on the basis of demands received in the JREDA office, request for supply/ installation will be communicated. Then within 45 days the supplier will have to ensure pre dispatch inspection from JREDA and within next 15 days JREDA will issue Dispatch instruction. Accordingly, the work of supply & installation will be completed by the vendor within 180 days’ period from the date of issue of work order. The bidders shall have no claim regarding economy of scale, choice of district/s or choice of region in the state, for the purpose of transportation of items/materials to the demand/work sites.
- For Participating Bidder ,the appliances to be Provided for Installation and Commissioning must be of reputed Companies make such as Solar PV modules, Battery and PCU etc. The Bidder must submit PDI request for the following Components for Dispatch clearance i.e Module and Battery.

Preventive/Routine Maintenance:

This shall be done by the supplier/contractor at least once in every month and shall include activities such as, cleaning and checking the health of the SPV system, cleaning of module surface, topping up of batteries, tightening of all electrical connections, regular checks to identify any leakage of electricity, changing of tilt angle of module mounting structure, cleaning & greasing of battery terminals and any other activity that may be required for proper functioning of the Solar Photovoltaic Power Plant. The maintenance record should be kept properly and to be submitted at JREDA office time to time. CMC documents should be certified by Beneficiary.

6. Timeline/ Completion Period:

The timeline for incorporation of all the requirements as per the clauses of scope of work shall be 4 months from the date of issuance of demand note and shall be in line with the following table:

Sl. No	Activity/Deliverables	Timelines for Solar Mini Grid Plant
1	Issuance of Letter of Award (LoA) to the contractor	X Days
2	Signing of Agreement between JREDA & Contractor	X+ 30 Days
3	Call for Pre Dispatch Instruction	X+ 45 Days
4	Issuance of Dispatch Instruction by JREDA	X+60Days
5	Delivery of Material on Site	X+100 Days
6	Installation & Commissioning	X+180 Days

7. Payment terms and conditions:

Subject to any deduction which JREDA may be authorized to make under this contract, the successful contractor shall be entitled to payment as per given payment Schedule defined in the table below: -

Sr. No.	Activity/Deliverables	Payment Schedule
1	Supply and delivery of goods	56% of Work order Value
2	Installation, Testing & Commissioning of complete Project	24% of Work order Value
3	Completion of every one-year period of the 5 year CMC period.	4% of Work Order Value per year (4% for 5 years = Total 20%)

Details of Payment terms and conditions as follows: -

- (a) **56%** of the of Contract price shall be paid **after supply and delivery of goods** in full and in good condition as certified by Consignee and/or JREDA Officials after submission of following documents:
- Copy of Original Commercial invoice raised at the time of supply in triplicate (1+2).
 - Copy of duly raised delivery challan / transportation challan /lorry receipt/dispatch clearance.
 - Duly filled **Annexure-11** should be submitted in three sets (one for Consignee record, one for JREDA Hq. and one for JREDA's field Executive Engineer).
 - Geo-tagged Photographs of all the equipment (materials) at destination with signature & seal of Consignee/JREDA Officials. This record should be kept in the office of Consignee for verification.
 - Submission of the E-Way Bill (EWB), generated for transportation of major components. i.e Solar Modules, Batteries and Inverter from the manufacturing unit to required site location in accordance with E-way Bill guidelines.
 - Submission of Transit Insurance Documents and Warranty Certificates of the Components.
- (b) **24%** of the of Contract price shall be paid **after Installation, Testing & Commissioning** of complete project after submission of following documents:
- Original Commercial invoice raised from the state of Jharkhand for the Installation, Testing & Commissioning made in triplicate (1+2).
 - Copy of duly raised challan / transportation challan /lorry receipt/dispatch clearance.
 - Duly filled **Annexure-12** should be submitted in three sets (one for Consignee record, one for JREDA Hq. and one for JREDA's field Executive Engineer).
 - Certificate for minimum seven days of satisfactory performance with Geo-Tagged Photographs of each Solar Mini grid village along with soft copy (Pen drive).
 - Hard Copy of 7 days system performance Report downloaded from RMS Portal.
 - Online generation data for last seven days through RMS from PCU. In case of unavailability of cellular network than agency have to submit declaration regarding unavailability of cellular network and have to submit running status of the system with Geotag Photographs and 7 days Generation data.
 - Submission of the Detailed Project commissioning Report in Booklet form.
 - Insurance paper of each installed Solar Mini/micro grid power plant with complete system.
- (c) Rest **20%** of the Contract Price shall be paid **@4%** of the Contract Price on completion of every one-year period of the 5 year CMC period. Payment for CMC can be released after submission of duty pledged DD/BG/FDR/TDR of 4% for each year valid up to CMC period. The BG/FDR will be release after submission of CMC documents in prescribed format. The Payment shall be released after submission of following documents:
- Original Commercial invoice raised from the state of Jharkhand for the supply made in triplicate (1+2).

- ii. Submission of Quaterly monthly reports of CMC undertaken by the manufacturer as per **Annexure-13 along with Monthly Generation Report (Annex-18)**

The payment for the items to be procured/installed will be released on availability of funds.

- (d) "The efforts will be made by JREDA to make available the due payments to the agency within three months against satisfactory completion of the work."
- (e) In case agency fails to comply CMC as per work order i.e., fails to submit CMC report or fails to attend compliance then after two notice or two months whichever is earlier, 2nd part of work order will be transferred to any of the technically qualified agency under that NIB on quotation basis and the performance bank guarantee of the agency will be forfeited along with necessary action as per prevailing rules.
- (f) JREDA reserve the right to pay agencies against submission of DD/BG/FDR of equivalent value of 2nd part of Project cost (CMC) valid till CMC period of the System.

Note :- Successful bidders who are awarded the work, shall at the time of submission of bills for payments, be required to submit e-way bills for verification to authenticate the invoices raised. Additionally, they must provide complete details of GST Input Tax Credit (ITC) for validation purposes. Further, as and when required bidders may be required to share access credentials, including passwords, with work Incharge/authorized representatives of JREDA for verification, along with relevant physical supporting documents. Processing of payments shall be strictly subject to satisfactory verification of all such records

8. Agreement:

The successful qualified bidders shall have to enter into an agreement in the office of the Director, JREDA, in prescribed format before commencement of the service.

9. Income Tax:

Without prejudice to the obligations of the contractor under law, any income tax which JREDA may be required to deduct by law/statute, shall be deducted at source and shall be paid to income tax authorities on account of the contractor. JREDA shall provide the contractor certificate for such deductions of tax.

10. Other responsibility of Successful Bidder: Notwithstanding anything mentioned in the specifications or subsequent approval or acceptance of the DDG system by JREDA, if at all, the ultimate responsibility for satisfactory performance of the entrusted Work shall rest with the Successful Bidder.

11. Cancellation of Work Order:

JREDA will be at liberty to terminate/blacklist in part or full the awarded contract without prejudicing its rights and affecting the obligations of the Contractor by giving 15 (Fifteen) days' notice in writing in the following events:

- (a) If the contractor/supplier is found defaulter for delays in supply of services to JREDA as per the Scope of Work.
- (b) If the contractor/supplier fails to comply with the provision(s) of the contract including the responsibilities to fulfill the 5 years CMC as per the provisions mentioned.

- (c) If the Contractor/vendor is involved in any action of moral turpitude.
- (d) If at any time, during the tendering process or after award of work, any of the documents/information submitted by the bidder is found to be incorrect, false or untruthful, the bid and/ or the resultant order may be summarily rejected/cancelled at the risk of the bidder and EMD/SD will be forfeit and bidder will have blacklisted.

12. Jurisdiction of the Court:

All disputes would be settled within Ranchi jurisdiction of court of law only.

13. Confidentiality

The contractor shall maintain utmost confidentiality of information supplied method of operation, procedure etc. and shall not make or allow to make an unauthorized copy, use, access or other utilization of these materials commercially or otherwise, directly or indirectly except as agreed to by JREDA.

This confidentiality will be maintained by the contractor for a period of two years from the date of service level agreement. The bidder shall follow the standard information systems of security policies and Govt. of India guidelines.

Section-6: Technical Specification

A) Technical Specifications of Components for Mini/Micro Grid System with Distribution Network to Household

1. Solar photo voltaic modules:

- 11** SPV modules and BOS including power conditioners/inverter, charge controller/ MPPT units, storage batteries, cables used in SPV power generation plant should strictly have minimal technical requirement/ standards as per latest MNRE guidelines. Technical specifications defined in this section notwithstanding, the most recent technical specifications of MNRE, till the time of submission of Bid, shall supersede the specifications defined in this Bid document and Bidders shall have to abide by the same. The Bidders are advised to keep themselves updated regarding the same.
- 12** If specifications of any component are not provided/mentioned in Rfp documents, the same shall be in line with latest BIS/ IS/ IEC specifications applicable at the time of submission of Bid.

2 Technical specification for Solar PV Module / Array:

- 21** Solar Photo Voltaic (SPV) modules/ array shall be of high efficiency made of Crystalline silicon SPV Modules shall also satisfy the MINIMAL TECHNICAL REQUIREMENTS / STANDARDS FOR SPV SYSTEMS. Office Memorandum of Ministry of New & Renewable Energy (MNRE) issued "Approved Models and Manufacturers of Solar Photovoltaic Modules (Requirements for Compulsory Registration) Order, 2019 and Amendment – reg. is applicable for supply of SPV Module.
- 22** The terminal box on the module should have a provision for opening for replacing the cable, if required.
- 23** The rating of each individual module should not be less than **500Wp** at Standard Test conditions (Higher ratings can be used) and shall meet following minimum requirement:
 - Efficiency of module ≥ 19.5%**
 - Fill factor shall be greater than 77%.**

General requirements for PV module:

- a. Only Indigenous Mono Crystalline SPV modules shall be used with minimum efficiency of 19%
- b. The interconnected cells shall be laminated in vacuum to withstand adverse environmental conditions

- c. The module frame is made of corrosion resistant materials, preferably having aluminum anodized finish
- d. The minimum clearance between the lower edge of the modules and the developed ground level shall be 300 mm.
- e. Surge arresting device to be provide at junction box and module shall be provided with bypass diode.
- f. The SPV module must be IEC 61215, IEC 61730 Part I and Part II, IEC 61701 certified from any of the accredited certifying agencies.
- g. Each solar PV module shall be warranted by the manufacturer for at least 90% of its rated power after initial 10 years and 80% of its rated power after 25 years from the completion of the trial run.
- h. Each PV module deployed must use a RF identification tag. The following information must be mentioned in the RFID used on each module. (This can be inside or outside the laminate but must be able to withstand harsh environmental conditions).
 - 2.3.1 Name of the manufacturer of the PV module
 - 2.3.2 Month & year of the manufacture (separate for solar cells and modules)
 - 2.3.3 Country of origin (separately for solar cells and module)
 - 2.3.4 I-V curve for the module
 - 2.3.5 Wattage, I_m , V_m and FF for the module
 - 2.3.6 Unique Serial No and Model No of the module
 - 2.3.7 Date and year of obtaining IEC PV module qualification certificate
 - 2.3.8 Name of the test lab issuing IEC certificate
 - 2.3.9 Other relevant information on traceability of solar cells and module as per ISO 9001.

3 Warranties

3.1 Material Warranty:

Material Warranty is defined as: The manufacturer should warrant the Solar Module(s) to be free from the defects and/or failures specified below for a period not less than five (5) years from the date of sale to the Bidder.

3.2 Defects and/or failures due to manufacturing

3.3 Defects and/or failures due to quality of materials

3.4 Non- conformity to specifications due to faulty manufacturing and/or inspection processes.

If the solar Module(s) fails to conform to this warranty, the manufacturer will repair or replace the solar module(s).

4 PCU/ Inverter

These solutions are required to provide uninterrupted power to 1P/ 3P AC loads using the various powers sources (PV, Grid etc.) directly or indirectly through battery storage. As SPV array produces direct current electricity, it is necessary to convert this direct current into alternating current and adjust the voltage levels to match the grid voltage. Conversion shall be achieved using an electronic Inverter and the associated control and protection devices. All these components of the system are termed the "Power Conditioning Unit (PCU)". In addition, the PCU shall also house MPPT (Maximum Power Point Tracker), an interface between Solar PV array & the Inverter, to the power conditioning unit/inverter. The power conditioning unit should also have provision of charge controller in case of systems with battery backup If necessary. Inverter output should be compatible with the grid frequency.

The system consists of a single cabinet housing all the necessary components – MPPT Chargers, Grid Charger, Inverter, Changeover circuit, ACDB & Remote Monitoring System in a single IP54 type cabinet suitable for outdoor mounting.

System Working: The solution should provide uninterrupted AC power to loads from various power sources connected to it like PV, Battery. It should also have possibility to connect to grid supply (synchronize & export) whenever available at site in future. The unit should always work in PV priority mode such that PV power is utilized to maximum and only. Some of the salient features of operation are as below:

- a. Inbuilt Single/ Multi MPPT charger for maximum PV generation and using the generated DC power for battery charging and meeting the loads.
- b. Inbuilt AC-DC convertor to utilize Grid power to charge batteries and cater to loads in bypass mode.
- c. Inbuilt DC-AC convertor so as to convert battery power and PV power into AC and meet the loads. Inverters should also have the facility to export excess PV power back into the grid whenever grid power is available.
- d. Automatic changeover arrangement between Inverter & grid so as to ensure uninterrupted power to AC loads.
- e. Remote Monitoring System which provides complete monitoring and automation of all the elements of plant, battery bank as well as various sections of PCU.

5 SOLAR CHARGE CONTROLLERS:

1. Single/ Multi MPPT Chargers should be convert PV power in to suitable DC power to charge batteries as well as provide DC power to Inverter input.
2. Solar Charge controllers shall be MPPT type only so as to extract maximum PV power from solar modules under varying weather conditions.
3. Three Stage battery charging (Float, Boost, equalize) should be provided for extended battery life along with features like battery current limiting, DC over voltage, DC under Voltage, PV reverse polarity protection etc.
4. In case of multi MPPT Chargers there should be active sharing between the modules so as to ensure that all the modules are equally loaded.
5. All the MPPT chargers must communicate with the master controller of the unit so as to ensure proper sharing between the various elements of the system.
6. All the parameters of the MPPT Chargers like PV Voltage, PV Amps (total), battery voltage, battery amps, battery status (Charging/ discharging) should be available on the front side of the unit through common display unit or through digital meters.
7. Circuit breakers to be provided at the input of each MPPT Chargers and at battery input.
8. All the parameters of the MPPT chargers should be available for remote monitoring on the RMS along with facility to control the critical parameters remotely.

6 SOLAR INVERTER:

1. Full capacity inverter should be provided to convert PV/ battery power into suitable AC power (230V/ 1P or 415V/ 3P +N) depending upon the requirement. Inverter should be a single inverter of full capacity or multiple inverters of smaller capacity to meet the full rating for the entire temperature range of 0-50 degrees.
2. Inverter should be microprocessor based with inbuilt power transformer so as to provide isolation between DC and AC side.
3. Inverter should have inbuilt protections against DC under voltage, DC over voltage, AC under voltage, AC over voltage, AC over frequency, AC under frequency.
4. All the inverter parameters, faults, warnings should be displayed on a central display unit visible from the front side.
5. Inverter should have the facility to cater to loads as well as export excess PV power into the grid. For this purpose, Inverter should have the facility to synchronize with the grid supply whenever grid is within its range of voltage (+/- 15% of nominal) and frequency (+/- 3 Hz). The functionality of exporting excess power should be field selectable for the end customer.

Typical technical features of the inverter shall be as follows:

Switching devices	IGBT/MOSFET
Control	Microprocessor /DSP
Nominal AC output voltage and frequency (In case single phase inverters are offered, suitable arrangement for	415V, 3 Phase, 50 Hz
Grid Frequency Synchronization range	± 3 Hz or more
Ambient temperature considered	-20° C to 50° C
Humidity	95 % Non-condensing
Protection of Enclosure	IP-20(Minimum) for indoor. IP-65(Minimum) for outdoor.
Grid Frequency Tolerance range	± 3 or more
Grid Voltage tolerance	20% &± 15 %
No-load losses	Less than 1% of rated power
Inverter efficiency(minimum)	>93% (In case of 10kW or above)
Inverter efficiency (minimum)	> 90% (In case of less than 10 kW)
THD	< 3%
PF	> 0.9

7 REMOTE MONITORING

All the relevant parameters of PCU should be available for remote monitoring over internet using GPRS (4G/5G enabled) based monitoring solution. PCU shall have GPRS (4G/5Genabled) inability based on SIM card which shall be provided by the bidder. The monthly charge of SIM card will be borne by bidder. The list of parameters should include:

Solar Charge Controller	PV Voltage, PV Current, PV Power, Daily PV Generation, Total PV Generation. (All above parameters to be included for all MPPT channels individually)
Inverter/ Mains Charger	<ul style="list-style-type: none"> • Inverter Voltage, Current, Frequency • Mains Voltage, Current, Frequency • Battery Voltage, Current • Daily & total Battery charging energy (kWh) • Daily & total Battery discharging energy (kWh) • Daily & Total load energy consumption(kWh) • Daily & Total energy import energy from Grid(kWh) • Daily & Total energy export energy from Grid(kWh) • Active Faults

8 SOLAR HYBRID INVERTER/PCU

Sl. No.	PARAMETERS	SPECIFICATIONS
1	Output Voltage	230V for single phase and 230/415Volts \pm 1% three phase, 4 wire output for three phase.
2	Output Frequency	50Hz \pm 0.5% during standalone Inverter/PCU operation. Inverter/PCU to follow generator frequency up to \pm 3 Hz of the nominal output frequency during synchronized operation
3	Rating	as stated below from 03KW -150KW
4	Surge Rating	Up to 150% of the continuous rating for a minimum of 5 seconds
5	Waveform	Sine wave output
6	THD	Less than 4%
7	Efficiency	>90% peak efficiency for single phase units. >92% peak efficiency for three phase units.
8	Regulation	Better than 2%
9	Phase Load imbalance	100% between phases for 3 phase units.
10	Internal Protection System	<ul style="list-style-type: none"> • Inverter/PCU overload • Short circuit protection • Over/under AC voltage protection • Over/under frequency protection • Over/under battery voltage protection
11	Front Panel Display (Inverter/PCU)	<ul style="list-style-type: none"> • PV Volts, Amps, Power. • Inverter/PCU O/P Voltage, Current, Frequency • Mains Voltage, Current, Frequency • Battery Voltage, Current • Mode of Operation, Active Faults • Mimic diagram
12	Circuit Breakers	<ul style="list-style-type: none"> • PV (each Channel) • Battery • Mains • Load
13	Temperature Range	0-50 degrees ambient
14	Humidity	0-90% non- condensing
15	Enclosure	IP-20 minimum

16	Data Logging	All the relevant parameters should be stored periodically in a USB stick/ pen drive/ flash drive to analyse the present and past data
17	Event Scheduling	<p>It should be possible to set events on a 24 hour scale. The events shall include:</p> <ul style="list-style-type: none"> ➤ Sleep Mode. ➤ Grid charge ➤ Grid Disconnect. ➤ Grid Export. ➤ Shut Down. <p>If configured, these events will force the PCU to enter that particular mode.</p>

1. REMOTE MONITORING

All the relevant parameters of PCU should be available for remote monitoring/ controlling over internet using GPRS based monitoring solution. The list of parameters should include:

1	Solar Charge Controller	PV Voltage, PV Current, PV power, Daily Generation, Total Generation. (all above parameters to be included for all MPPT channels individually)
2	Inverter/PCU/ Mains Charger	<ul style="list-style-type: none"> • Inverter/PCU Voltage, Current, Frequency, Daily Generation, Total Generation. • Mains Voltage, Current, Frequency • Battery Voltage, Current • Active Faults

Important NOTE**

1. All the important remote monitoring parameters are available over the internet using GPRS (2G/3G/4G enabled) based solutions. The RMS shall be able to push the information to the web server for every 15 minutes even under the 2G networks.
2. There should be facility to turn on/ off the unit remotely using GPRS based monitoring solution. All the data should be downloadable in form of excel sheets from the portal. The portal should be accessible from anywhere through a URL, user ID and password. All the data should also be accessible locally through USB port or pen drive.

Other important Features:

- a) Three phase hybrid PCU shall be used with each power plant system.
- b) PCU shall be capable of complete automatic operation including wake-up, synchronization & shutdown.
- c) (c)Inverter/PCU should have internal protection arrangement against any sustainable fault in feeder line and against the lightning on feeder.
- d) Built-in meter and data logger to monitor plant performance through external computer shall be provided.
- e) Anti-islanding (Protection against Islanding of grid): The PCU shall have anti islanding protection inconformity to IEEE 1547/UL 1741/ IEC 62116 or equivalent BIS standard.

- f) The MPPT units environmental testing should qualify IEC 60068-2 (1, 2, 14, 30)/ Equivalent BIS std. The junction boxes/ enclosures should be IP 65 (for outdoor)/ IP 54 (indoor) and as per IEC 529 specifications.
- g) The PCU/ Solar Inverter/PCUs should be tested from the MNRE approved test centers/ NABL/ BIS/ IEC accredited testing- calibration laboratories. In case of imported power conditioning units, these should be approved by international test houses.
- h) Inverter/PCU shall be applicable to operate in the both offline and online mode so that if export facility is Required then it can be converted in to grid export mode.

AC-DC Convertor for Grid Charging.

1. Rectifier cum AC-DC convertor for charging batteries from Grid should be an integral part of the system. There can be separate rectifier units or the inverter should be used in a bidirectional manner to implement this functionality.
2. Battery charging should be of 3 stage type (float, boost, equalize) so as to ensure long life of the battery.
3. AC-DC convertor should be able to work with Grid in the entire range of voltage (150V-270V) and frequency (47-53 Hz). Any additional circuitry of required to achieve the above functionality should be a part of PCU itself.
4. It should inbuilt protections for AC Under Voltage/ Over Voltage, AC Under frequency/ Over Frequency, O/P Short Circuit, Battery over Voltage, Battery under Voltage etc.
5. All the parameters and faults should be displayed on a common display unit on the front panel.
6. Three Phase PCU/inverter shall be used with each power plant system (10kW and/or above) but in case of less than 10kW power plant system single phase inverter shall be used.
7. PCU/inverter shall be capable of complete automatic operation including wake-up, synchronization & shutdown.
8. The output of power factor of PCU inverter is suitable for all voltage ranges or sink of reactive power, inverter should have internal protection arrangement against any sustainable fault in feeder line and against the lightning on feeder.
9. Built-in meter and data logger to monitor plant performance through external computer shall be provided.
10. The power conditioning units / inverters should comply with applicable IEC/ equivalent BIS standard for efficiency measurements and environmental tests as per standard codes IEC 61683/IS 61683 and IEC 60068-2(1,2,14,30) /Equivalent BIS Std.
11. The charge controller (if any) / MPPT units environmental testing should qualify IEC 60068-2(1, 2, 14, 30)/Equivalent BIS STD. The junction boxes/ enclosures should be IP 65(for outdoor)/ IP 54 (indoor) and as per IEC 529 specifications.
12. Less than 10 kW PCU/inverter shall be tested from the MNRE approved test centers/NABL/BIS/IEC accredited testing-calibration laboratories. In case of imported power conditioning units, these should be approved by international test houses.
13. PCU/inverter shall be tested from the MNRE approved test centers/NABL/BIS/IEC accredited testing-calibration laboratories.

a. Data acquisition system/ plant monitoring

Considering the nature of sites which are located remotely and generally unmanned hence all the data of site has to be made available **remotely on a Web server for monitoring** as well as control. **The remote monitoring system** should have below features:

1. Data of all the equipment's at sites (MPPT, Inverter, Charger, Battery Bank shall be available in a common bus preferably MODBUS 485. All this data should be input to the local modem housed inside the Inverter cabinet.
2. The modem should have capability to connect with 3G/ 4G/5G network via SIM card and send all the local data to server. It would be preferred to have dual SIM card slots for redundancy. IT should also have required antennae for signal transmission.
3. In addition to sending data remotely there should be facility to store same data locally as well so as to fetch data from weak network areas. During network failure local storage should act as buffer storage and once network resumes then data from the buffer period should be fetched back to server to avoid any loss of data.
4. The modem will draw supply from inverter/ battery bank in an uninterrupted manner such that even if inverter has failed, modem should continue to report the conditions remotely.
5. All the data should be shared remotely on 3rd part server and end customer can access data from all the sites using a common login and password.
6. The User interface should be designed in a user friendly manner with a dashboard page which shows all the lives sites along with status of power sources, faults, GPS mapping and energy graphs.
7. End user should be able to get insight of individual sites by clicking on them where they can access live status of power flow, power, energy and other parameters along with past history.
8. Facility of getting data history of individual sites should be possible along with auto generated daily reports.
9. For trouble shooting purpose it should be possible to find event history of each site in reverse chronological order.
10. It should be possible to control events like Inverter On & Off, Load On and OFF etc. from the remote portal itself
11. In case any fault occurs there should be facility to communicate the same through SMS/ E-Mail/ Weber to the allocated numbers of end user. The ticket raised should have site details, unit ID along with nature of fault. In case the fault is not closed in stipulated time then there should be facility to escalate it to higher level through auto generated email/SMS Weber to pre fixed numbers or email id. This is call ticketing system.
12. All the data should also be accessible locally through USB port or pen drive.
13. From reliability point of view and avoid theft like activities at site faults like Door open (for battery and inverter separately), Smoke, module level failures, additional AIO/ DIO (2 Nos each) integration of Weather sensors (1 irradiation and 1 wind sensor) and web cam integration should be possible.

14. Successful Bidder shall install appropriate Time-of-Day (ToD) meter at Site to keep record of 15- minute time block-wise generation and supply of electricity. For this purpose, the standard and specifications of the meter shall be at par with those recommended by electricity distribution companies of Jharkhand suitable for generation and supply from plants of the size of Project.

15. The meter should have capacity to store 15-minute time block-wise data on generation and supply for 40-45 days and day-wise data on generation and supply for 6 months in such a form as to help Engineer download it using MRI.

b. There should be an easily accessible emergency stop switch.

c. Protection and safety

i. Specifically, the inverter should be three phase static solid state type power conditioning unit. Both AC & DC lines shall have suitable MCB/MCCB and Contractors to allow safe start up and shut down of the system. PCU should have protections for overload, surge current, high Temperature, over / under voltage and over / under frequency & reverse polarity. The complete operation process & safety instructions should be printed on the sticker & suitably pasted on the PCU. The inverter shall have provision for input & output isolation (automatic & manual).

ii. Each solid state electronic device shall have to be protected to ensure long life of the inverter as well as smooth functioning of the inverter. Inverter should have safety measures to protect inverter from reverse short circuit current due to lightening or line faults of distribution network.

iii. PCU should be suitably placed in control room on a suitable wooden or concrete platform with complete safety measure as per norms.

d. Battery Bank

The batteries shall be for SPV application Lead Acid type AGM-VRLA or Tubular Gel, or Lithium ferro Phosphate Battery Bank voltage will be 24V/48V/96V/120V/240V/480V or as per design. The general specifications shall be as under:

1. The battery bank shall consist of required number of deep-discharge electrochemical storage cells, suitably interconnected as required. Parallel connections of storage cells will be discouraged.
2. The batteries shall use 2V battery capacity to be designed for C10 rate.
3. The cells shall be capable of deep discharge and frequent cycling with long maintenance intervals and high columbic efficiency. Automotive or car batteries shall not be accepted.
4. The nominal voltage and capacity of the storage bank shall be selected and specified by the supplier in the Bid.
5. The self-discharge rate of the battery bank or individual cell shall not exceed four (4) percent per month.
6. The permitted maximum Depth of Discharge (DOD), shall not be more than 80%.
7. The cells shall include explosion proof safety vents.

8. Suitable number of corrosion resistant storage racks shall be supplied to accommodate the cells tester and other accessories. The rack design shall be such that minimum space is required, without any way obstructing the maintenance requirements. For metallic racks, standards specified for control panel enclosures and other metallic shall govern.
9. All the connectors should be insulated except for the end portions.
10. Charging instructions shall be provided along with the batteries.
11. A suitable battery rack with interconnections & end connector shall be provided to suitably house the batteries in the bank.
12. The batteries shall be suitable for recharging by means of solar modules via incremental / open circuit regulators.
13. Battery interconnecting links shall be provided for interconnecting the battery in series and in parallel as needed and shall be Lead coated heavy duty copper strips.
14. Connectors for inter cell connection (series / parallel) shall be maintenance free screws. Front covers shall be provided for each battery bank.
15. The operating range will be 0°C to +55/60°C.
16. AH Efficiency: >95% and WH Efficiency: >85%
17. Recombination Efficiency shall be >98%
18. Self-Discharge of battery shall be <0.5% per week at 27°C.
19. The minimum rating of battery voltage (V) and Ah at C10 rate of discharge of different villages should be as following:

S. No	Capacity of Power Plant (kW)	Battery Bank Voltage	Battery capacity Ah @8.4 VAH/Wp
1	1	48	175
2	2	48	350
3	3	48	525
4	4	48	700
5	5	96	437.5
6	6	96	525
7	7	96	612.5
8	8	96	700
9	9	96	787.5
10	10	120	700
11	15	240	525
12	20	240	700
13	25	240	875
14	30	240	1050
15	40	240	1400
16	50	240	1750
17	60	240	2100

18	70	240	2450
19	80	240	2800
20	90	240	3150
21	100	240	3500

Battery Rack

Battery rack should be of matured treated Salwood duly painted single tier or two tier (if required) or epoxy coated MS structure (for VRLA GEL Cells) with rubberized coating on battery runners. Placement of battery should be such that maintenance of the battery could be carried out easily. The non-reactive acid proof mat should be provided to cover the entire floor space covering the battery rack. Battery rack should compulsorily be placed on the appropriate rubbers pads to avoid the contact of racks with the floor, and to protect wooden rack particularly from termite.

BATTERY- Lithium ferro Phosphate:

The battery should Lithium Ferro phosphate (Lifepo4) having capacity as motioned below at standard conditions. The battery Voltage & AH can be changed keeping the overall KWH same. The voltage selection should be close to Vm of combinations of modules having 72/144 cells. The configuration of battery assembly should be as per requirement of capacity. The cell should be prismatic type having capacity not less than 40 Ah. The other feature of the battery should be:

S.N.	Description	Specification
1	Battery Configuration minimum cell capacity	3.2V- 40 AH; LiFePO4
2	Working Temperature Range (both for charging & discharging)	0-60 Deg C
3	Storage Temperature Range	@ 0-40 Deg- 6 months
4	Cycle Life (Full charge to full discharge @ 25 deg C before capacity of battery falls below 75%)	≥ 3000 Cycles
5	Battery Warranty	The LFP batteries shall be warranted for at least 5 years.
6	Type of Cell	Prismatic

- Depth of Discharge: minimum 90%
- Maximum Discharging rate: up to C/3 rate of battery Capacity
- Maximum Charging Rate: upto C/2 rate of battery capacity

The Lithium Ferro phosphate battery needs a very good “Battery Management Systems” BMS to ensure the proper charging and discharging of each cell of battery with temperature

compensation. This battery also needs constant current and constant voltage charging methodology related to upper voltage limit of battery. BMS primary focus is therefore on the safety and the protection of the battery pack, to minimize the risk of sudden failure and to maximize the life cycle of the battery. The secondary

function of the BMS is to perform battery diagnosis, such as state of charge (SOC) estimation, state of health (SOH) estimation and state of power (SOP) estimation. Hence a very good battery management system to be incorporated and got it tested with battery from MNRE/NABL accredited lab as per IEC/BIS standard. The BMS of the LFP battery must also communicate with PCU in some standard protocol like RS485/ 232 or CAN so that PCU can adapt to requirements of battery and extend its life. Communication between PCU and BMS and the compatibility of 2 should be ensured.

The Valid test report as BIS of at least 3.2-volt 40 Ah cell from MNRE/NABAL accredited lab should be submitted along with tender.

Integration of SPV power plant with grid

- a) The output power from SPV would be fed to the inverters which converts DC produced by SPV array to AC and feeds it into the main electricity grid after synchronization.
- b) In case of grid failure, or low or high voltage, solar PV System shall be out of synchronization and shall be disconnected from the grid. The supply would be resumed from battery bank or once the grid comes into service PV system shall again be synchronized with grid supply and load requirement would be met to the extent of availability of power. 4 pole isolation of inverter output with respect to the grid power connection need to be provided.

Array structure

- i. Hot dip galvanized MS mounting structures may be used for mounting the modules/panels/arrays. Each structure should have angle of inclination as per the site conditions to take maximum insolation. However, to accommodate more capacity the angle inclination may be reduced until the plant meets the specified performance ratio requirements.
- ii. The Mounting structure shall be so designed to withstand the speed for the wind zone of the location where a PV system is proposed to be installed (for minimum wind speed of 150 km/ hour). Suitable fastening arrangement that do not require drilling in roof tops should be adopted to secure the installation against the specific wind speed.
- iii. The mounting structure steel shall be as per latest IS 2062: 1992 and galvanization of the Mounting structure shall be in compliance of latest IS 4759.
- iv. Structural material shall be corrosion resistant and electrolytically compatible with the materials used in the module frame, its fasteners, and nuts and bolts. Aluminum structures also can be used, that can withstand the wind speed of respective wind zone. Necessary protection towards rusting need to be provided, either by coating or anodization.
- v. The fasteners used should be made up of stainless steel. The structures shall be designed to allow easy replacement of any module. The array structure shall be so designed that it will occupy minimum space without sacrificing the output from the SPV panels.
- vi. Regarding civil structures, the Bidder need to take care of the load bearing capacity of the roof (if require) and need to arrange suitable structures based on the quality of roof.

- vii. The total load of the structure (when installed with PV modules) on the terrace should be less than 60 kg/m².
- viii. The minimum clearance of the structure from the roof (if require) level should be 300 mm

i Lightning and over voltage protection

The SPV power plants shall be provided with lightning & overvoltage protection. The main aim in this protection shall be to reduce the over voltage to a tolerable value before it reaches the PV or other sub system components. The source of over voltage can be lightning, atmosphere disturbances etc. The entire space occupying the SPV array shall be suitably protected against Lightning by deploying required number of Lightning Arrestors. Lightning protection should be provided as per IEC 62305 standard. The protection against induced high-voltages shall be provided by the use of Metal Oxide Varistors (MOVs) and suitable earthing such that induced transients find an alternate route to earth.

ii Surge Protection

Internal surge protection shall consist of three MOV type surge-arrestors connected from +ve and -ve terminals to earth (via Y arrangement)

iii Earthing protection

Each array structure of the PV yard should be grounded/ earthed properly as per IS: 3043- 1987. In addition, the lighting arrester/masts should also be earthed inside the array field. Earth Resistance shall be tested in presence of the representative of Department as and when required after earthing by calibrated earth tester. PCU, CAD and DC DB should also be earthed properly.

Earth resistance shall not be more than 5 ohms. It shall be ensured that all the earthing points are bonded together to make them at the same potential.

iv Array Junction Box (AJB)

This shall consist of suitable polycarbonate / powder coated metal casting. Array junction box allows several photovoltaic strings (from 8 to 32) to be connected in parallel. The total DC Power is then distributed to the photovoltaic inverter. It includes photovoltaic string protection, overvoltage protection and a DC output switch disconnected. In this box/boxes, a separate arrangement, consisting of SPDs and DC connector of suitable specifications for array, shall be made to help it with stand respective flow of current.

1. All the incoming PV strings should connect to the box through proper MC4 connectors on +ve and -ve side. Field side connectors should be provided as a part of the system so as to ensure proper connections.
2. The number of AJB inputs should be decided depending upon the number of strings along with one spare input.
3. All the incoming strings should have proper PV fuses on +ve and -ve side. Rating of fuses should be chosen depending upon the geographical location of the plant and short circuit current of string. All the fuses should be rated for minimum 1000V DC.
4. Type II SPD to be provided at the output of each AJB (input of each MPPT) for protections against lightning surges.

5. Proper isolator/ MCCB shall be provided at the output of each MPPT charger

v DCDB

DCDB shall be provided with the purpose of providing the option for isolating the battery bank. There shall be copper bus bars of suitable rating and can either be independent or integrated in PCU.

vi AC Distribution Board (ACDB)

This shall consist of box of suitable powder coated metal casting. One feeder per phase shall be provided in ACDB with MCB of suitable capacity installed at each feeder in the ACDB. One electronic energy meter, ISI make, single / three phase (as per requirement) of good quality shall also be installed in ACDB suitable placed to measure the consumption of power from SPV Power Plant. Proper rating MCB shall be installed at every feeder (in case of single phase output also, there shall be three feeders) to protect feeders from the short circuit current as per the requirement of the site & instructions of JREDA. A separate dedicated feeder from conventional line to PCU as well as ACDB should also be installed, as per JREDA's instruction.

A separate changeover switch of proper rating should also be suitably installed in the ACDB to isolate the existing connected load from solar system and cater the power to the existing load from convention power (Mains) in case of emergency. ACDB should be connected between PCU and Load.

vii Battery Protection Panel (BPP)

This shall consist of box of suitable powder coated metal casting. BPP should be installed to make provision to isolate the battery bank. Proper rating HRC fuse and MCCB/isolator for DC application should be suitably installed. BPP should be connected between battery bank and DCDB. This can be integrated in the PCU.

viii Danger Boards

Danger boards should be provided as and where necessary as per IE Act/IE Rules as amended up to date, as per the instructions of JREDA and affixed at various appropriate locations.

ix Cables/ wires

Cables of appropriate size to be used in the system shall have the following characteristics:

- i. Shall meet IEC 60227/IS 694, IEC 60502/IS1554 standards
- ii. Temp. Range: -10°C to $+80^{\circ}\text{C}$.
- iii. Voltage rating 660/1000V
- iv. Excellent resistance to heat, cold, water, oil, abrasion, UV radiation
- v. Flexible
- vi. Sizes of cables between array interconnections, array to junction boxes, junction boxes to Inverter etc. shall be so selected to keep the voltage drop (power loss) of the entire solar system to the minimum. The cables (as per IS) should be insulated with a special grade PVC compound formulated for outdoor use.

- vii. Cable Routing/ Marking: All cable/wires are to be routed in a GI cable tray and suitably tagged and marked with proper manner by good quality ferule or by other means so that the cable easily identified.
- viii. The Cable should be so selected that it should be compatible up to the life of the solar PV panels i.e. 25 years.
- ix. The ratings given are approximate. Bidder to indicate size and length as per system design requirement. All the cables required for the plant provided by the Bidder. Any change in cabling sizes if desired by the Bidder/approved after citing appropriate reasons. All cable schedules/layout drawings approved prior to installation.
- x. Multi Strand, annealed high conductivity copper conductor PVC type 'A' pressure extruded insulation or XLPE insulation. Overall PVC/XLPE insulation for UV protection Armored cable for underground laying. All cable trays including covers to be provided. All cables conform to latest edition of IEC/ equivalent BIS standards.
- xi. Description Standard Number Cables General Test and Measuring Methods, PVC/XLPE insulated cables for working Voltage up to and including 1100 V, UV resistant for outdoor installation IS /IEC 69947.
- xii. The size of each type of DC cable selected shall be based on minimum voltage drop however; the maximum drop shall be limited to 1%.
- xiii. The size of each type of AC cable selected shall be based on minimum voltage drop however; the maximum drop shall be limited to 2%.

1.23 Junction Boxes (JBs)

1.23.1 The junction boxes are to be provided in the PV array for termination of connecting cables. The J. Boxes (JBs) shall be made of GRP/FRP/Powder Coated Aluminum /cast aluminium alloy with full dust, water & vermin proof arrangement. All wires/cables must be terminated through cable lugs. The JB's shall be such that input & output termination can be made through suitable cable glands.

1.23.2 Copper bus bars/terminal blocks housed in the junction box with suitable termination threads Conforming to IP65 standard and IEC 62208 Hinged door with EPDM rubber gasket to prevent water entry. Single / double compression cable glands. It should be placed at 5 feet height or above for ease of accessibility.

1.23.3 Each Junction Box shall have High quality Suitable capacity SPDs, suitable Reverse Blocking Diodes. The Junction Boxes shall have suitable arrangement monitoring and disconnection for each of the groups.

1.23.4 Suitable markings shall be provided on the bus bar for easy identification and the cable ferrules must be fitted at the cable termination points for identification.

1.23.5 All fuses shall have DIN rail mountable fuse holders and shall be housed in thermoplastic IP 65 enclosures with transparent covers

1.24 Power Distribution Network

Installation & Supply of minimum Three (3) domestic light points along with 3 nos. LED lamps of 12W each & Installation of one socket point (60W) & one socket point (100 W) taken with

proper switching arrangement, in every selected house hold of the village with complete fittings of wiring in proper manner within conduit installed on saddle/ casing capping with prior approval from JREDA. House wiring should be done with Heavy duty wire/ cable.

P.V.C. Insulated twisted bright annealed Copper wire of 1.5 Sq. mm (3core) or 2.5 Sq. mm (2core) size every light point & socket point should be provided with individual switch of 6A rating and should be of reputed make.

1. Installation of domestic connection to every household shall be through service pipe as per the standard electrical fittings. It shall use cable of aluminum wire PVC insulated sheathed and single core cable (IS694/1990 of 6 sq.mm) of reputed make.
2. Installation of appropriate load limiting switch / fuse for controlling domestic / street lighting connections, as per requirement of the site.
3. Supply, installation & grouting of 8 meters MS Poles/tubular pole/PCC pole as per latest ISI/ JBVNL norms (or if the Bidder has better drawing he may attach the same with additional offer) for overhead / underground distribution network of cables at village/site. All poles/street lights should be numbered by oil paint in the specified format of JREDA. Two numbers of MS sign boards (each of 2' x 2.5' size) has to be supplied, painted (in the same manner as pole painting instructions) & clamped on the poles of the PDN as per JREDA's instructions.
4. Supply, installation & commissioning of cabling from pole to pole & pole to house. Cabling between pole to pole/ pole to house can also be done as per Bidder's design with prior approval of JREDA.
5. Supply, installation & commissioning of one number of 18 W LED AC Street light luminary.
6. Supply of 1 number of street light per 5 households.
7. Supply of 3 Nos. of 12W LED bulbs per HHs
8. Two Socket points for appliances like TV and mobile charging.
9. Supply & installation of earthing kits, stay wire sets with complete set for poles tc.as per norms where ever required.
10. **Size of Control Room as per given below: -**

Group	Size of Control Room Dimension(LXBXH) in ft
Group "A" 1 to 10 kWp	10 x 12x10
Group "B" 11 to 50 kWp	15 x 12 x10
Group "C" 51 to 100 kWp	21x 20 x10
Group "D" above 100 kWp	25 x20 x10

10. **Fencing:-** The contractor shall provide chain link fencing with barbed wire at top to protect the entire plant premises for restriction the entry of trespassers. The minimum height of the fencing at any point from ground shall be 1.5 mtr. The chain link of 50mm x 50mm diamond mesh of 10-gauge galvanized steel wire with 12-gauge barbed wires at top (02 numbers) is to be provided.

The Contractor's shall be supplying, fabricating and fixing aligning vertical post of 75mm x 75mm x 6mm with cross bracing both side of ISA 45mm x 45mm x 5mm and both bracing shall be fixed by nut bolt assembly at intersecting point. Also, line wire at top and bottom of chain link mesh of 8 gauge is to be provided. The chain link fencing shall be fixed in ground by minimum 450mm deep foundation. At bottom of the fencing, 230mm thick brick masonry of 150mm depth shall be provided to avoid entry of any animal from the bottom. The brick masonry shall be rested on 100mm thick of M15 grade Plain cement concrete. The brick masonry shall be covered by 12mm plaster in 1:4 Cement Mortar.

Note - All cables should be of copper, tested for general test and measuring method and PVC insulated cables as per IEC 60227 / IS 694 and IEC 60502 / IS 1554. All the materials to be consumed in the power distribution network should be of best quality confirming to specification and should be with prior approval of JREDA.

In case the length of the distribution network increases/decreases due to change in number of households in the villages, then the change upto $\pm 5\%$ should be accommodated in the same price quote. Over and above the change of $\pm 5\%$ the amount will be adjusted on the proportionate bases.

Changeover, Switchgear & Terminations (Protection and safety):

1. All Inputs and outputs should have proper circuit breakers in form of MCB/ MCCB. This includes Battery, PV (each MPPT), Load (separate in case of multiple outputs) etc.
2. All incoming PV strings should be through proper MC4 connectors along with supply of female counterparts as well.
3. Battery termination should be in form of single/ multiple set of bus bar type terminations depending upon the number of banks in parallel.
4. Load connections should be bus bar type terminals.
5. DC and AC side terminations/ switchgear should be in separate housings (both part of main housing) having PAD lock provisions along with proper cable clamping mechanism and Ip65 glands suited for battery sizes specified.

Proper SPD should be provided on PV, load and Grid path. (Load path should have Type-I+II SPD where others can have typical Type II SPD. In case of multiple outputs each path should have its dedicated SPD protection.

6. Automatic changeover should be ensured between inverter & Grid depending upon the availability of power sources or during failure so as to ensure uninterrupted power at load output.

Construction of Room for Inverter/ Battery:

The Contractor shall plan for sufficient no. of appropriately designed rooms for inverters/ Batteries or any other equipment as per the equipment's operating guidelines. The room(s) thus constructed shall have auxiliary power supply, electrical fixtures with all necessary protections for connection of the equipment inside. All civil work shall strictly follow relevant IS standards and REC's DDG guidelines.

Container (Optional):

1. The whole system (Battery, Inverter, firefighting System etc.) Shall be enclosed in a container or cabinet with IP-54 Class of Protection or as per national/ International Standards. (IEC-60529). The Systems must be placed in a container and it should have feature for heat load management the Standards containerized Solution including both battery and hybrid inverter shall be preferred. The System's Container shall meet all the standard safety requirements. Further, the container material should have electro- chemical compatibility and resistant to acid and alkaline material should be fire retardant and it shall be able to withstand the tensile stress due to internal pressure of the cells or electrolyte in the worst operating conditions.
2. The equipment's of solar power generation plant except PV Modules cell be housed in container as per relevant ISO Standards. The corrosion category of the container shall be as per relevant ISO Standards and location requirement.
3. Control room and battery bank shall be in a container of suitable size for housing of batteries and control system. The facilities must be properly ventilated and must have clear space for walking for at least one person between different rows of equipment. Minimum C4 Class paint cell be used for container to protect against Corrosive conditions.

Energy Meter:

- i. Energy meters shall be provided for measurement of electricity consumption of Solar Mini grid villages.
- ii. The meters shall be suitable for rural microgrid applications, ensuring accuracy, reliability.
- iii. Type: -single/Three Phase
- iv. As per latest relevant IS 13779 or relevant latest std. and should be compliance with CEA metering regulation as amended time to time.
- v. Key features: -Measure Voltage, current ,kWH

Annexure-1

Format for Covering Letter

NIB No: 03/JREDA/OFFGRID/RC/26-27

(To be submitted in the official letter head of the company)

To,

The Director,
Jharkhand Renewable Energy Development Agency
3rd Floor, S.L.D.C. Building,
Kusai Colony, Doranda,
Ranchi - 834002.

Sub Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand

Sir,

We are hereby submitting our offer in full compliance with the terms and condition of the above NIB No.under Category.....(General /MSEs /NEW MSEs).We have submitted the requisite amount of **Tender Fee & EMD through online mode (Receipt must enclosed)** as specified in the tender document. Earnest Money through online mode is valid for twelve months. Bid will be evaluated only for the applied category and no further claim for the change of category (Gen/MSE/New MSE) will be accepted.

The tender is uploaded on www.jharkhandtenders.gov.in as per the requirement of the website separately Technical Bid & Financial Bid.

Note: MSME bidders of Jharkhand must submit necessary documents for claiming exemption of EMD and Bid fee

(Signature of Authorized Signatory)

Name:

Designation:

Company Seal:

Annexure-2

Check List for Technical bid

NIB No: 03/JREDA/OFFGRID/RC/26-27

S. No.	Particulars	Uploaded Yes / No	File name	From Page No.... to page no.....
1	Covering Letter as per Annexure-1.			
2	Information about the Bidder as per Annexure-3.			
3	Declaration by Bidder as per Annexure-4.			
4	Average Annual Turnover for last three years ending 31.03.2025(Attach average annual turnover certificate as per Annexure-5)			
5	Net worth as on 31.03.2025. (Attach proof & Net worth certificate as per Annexure-6)			
6	Authority Letter for Signing Bid Document & Attending Bid Opening Meeting			
7	The proof of related work in any PSU/Govt. organization in the last Seven years as per NIB in Annexure-8. Attach copy of the order/work completion and certificate indicating its successful execution.			
8	To indicate the functionality of the firm, attach the balance sheet of last three years ending 31.03.2025(FY 22-23, FY 23-24& FY24-25) of the firm duly certified by statutory Auditor & ITR for AY (2023-24,2024-25 & 2025-26)			
9	A copy of valid GST registration certificate &PAN			
10	A copy of Valid Test Report of PCU, Battery and Module from any test center approved/recognized by MNRE approved Labs of the offered system as per NIB			
11	Details of EMD & Bidfee Deposit through online mode (Receipt Enclosed)			
12	Registration cert. of MSEs of Jharkhand/Details of DIC duly verified by GM DIC			
13	Contractor Registration Certificate			
14	Annexure 17(Declaration by Bidder)			
15	Other Relevant Documents as per NIB			

NOTE Please fill and upload respective documents file name and from page number....to page no.... and write it in the box.(Mandatory)**

Please ensure:

- i) That all information is provided strictly in the order mentioned in the check list mentioned above.
- ii) Bidders are advised to strictly confirm compliance to bid conditions and not to stipulate any deviation/conditions in their offer. Subsequent to bid submission, JREDA may or may not seek confirmations/clarifications and any offer(s) not in line with Bid conditions shall be liable for rejection.
- iii) Any clarification/confirmation bidder may require shall be obtained from JREDA before submission of the bid. Bidder shall submit complete bidding document including subsequent amendment, modification and revision, duly signed and stamped as a token of having read, understood and accepted all the terms and condition mentioned therein.

(Signature of Authorized Signatory)

Name:

Designation:

Company Seal:

Annexure-3

Format for Information about the Bidder

NIB No: 03/JREDA/OFFGRID/RC/26-27

Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand.

SL. No.	Particulars	
1.	Name of the Bidder	
2.	Address of Bidder with Telephone, Fax, email	
3.	Address of the Registered Office	
4.	Address of the works	
5.	GPS Co-ordinate of Registered Office	
6.	GPS Co-ordinate of Factory Campus	
7.	Name & Designation of Authorized Signatory for Correspondence (Attach Power of Attorney as per Annexure-7)	
8.	Nature of Firm (Proprietorship/Partnership /Pvt.Ltd./Public Ltd. Co./Public Sector)	
9.	Permanent Account Number (PAN)/TIN(Attach proof)	
10.	Firm's Registration Number (Attach proof)	
11.	GST Certificate (Attach proof)	
12.	Specify the Item Originally Manufactured (SPVmodule/PCU/Battery) (Attach copy of Registration Certificate of Industry Department)	
13.	Details of in-house testing facility(Attach Proof)	
14.	Office/ Dealer and Service network in Jharkhand with TIN No. (Give details)	
15.	Bidder Quoted for (Group A,B,C & D)	
16.	Total Quoted Capacity (kWp)	
17.	Particulars of Earnest Money	
18.	Place where Materials will be Manufactured	
19.	Place where Materials will be Available for Inspection	
20.	Other details and remarks, if any	

(Signature of Authorized Signatory)

Name:

Designation:

Company Seal:

Annexure-4

Declaration by the Bidder

NIB No: 03/JREDA/OFFGRID/RC/26-27

(To be submitted in the official letter head of the company)

I/We _____ (here in after referred to as the Bidder) being desirous of tendering for the rate contract for work under category/Group Name _____ (With Battery) and quote quantity [**quoted quantity/capacity**] _____

, the above mentioned tender and having fully understood the nature of the work and having carefully noted all the terms and conditions, specifications etc. as mentioned in the tender document, DO HEREBY DECLARE THAT

1. The Bidder is fully aware of all the requirements of the tender document and agrees with all provisions of the tender document.
2. **The bidder will quote in only one Group from Group A, B, C & D. If the bidder will quote in more than one category from Group A,B,C & D ,then bidder shall be liable to disqualification.**
3. The Bidder is capable of executing and completing the work as required in the tender.
4. The Bidder accepts all risks and responsibilities directly or indirectly connected with the performance of the tender.
5. The Bidder has no collusion with any employee of JREDA or with any other person or firm in the preparation of the bid.
6. The Bidder has not been influenced by any statement or promises of JREDA or any of its employees, but only by the tender document.
7. The Bidder is financially solvent and sound to execute the work.
8. The Bidder is sufficiently experienced and competent to perform the contract to the satisfaction of JREDA.
9. The information and the statements submitted with the tender are true.
10. The Bidder is familiar with all general and special laws, acts, ordinances, rules and regulations of the Municipal, District, State and Central Government that may affect the work, its performance or personnel employed therein.
11. The Bidder has not been debarred from similar type of work by any SNA/ Government Dept. /PSU.
12. This offer shall remain valid for Six months from the date of opening of the tender.
13. The Bidder gives the assurance to execute the tendered work as per specifications terms and conditions.
14. The Bidder confirms the capability to supply and install required no. of systems per month.
15. The Bidder accepts that the earnest money be absolutely forfeited by JREDA if the Bidder fails to undertake the work or sign the contract within the stipulated period.

(Signature of Authorized Signatory)

Annexure-5

Format For Financial Requirement – Annual Turnover

NIB No: 03/JREDA/OFFGRID/RC/26-27

To,

The Director,
Jharkhand Renewable Energy Development Agency
3rd Floor, S.L.D.C. Building,
Kusai Colony, Doranda,
Ranchi - 834002

Dear Sir,

Sub: Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand

We certify that the Bidding Company had an average Annual Turnover of Rs. -----
- based on audited annual accounts of the last three years ending 31.03.2025

Sl. No.	Financial Year	Turnover (in Rupees)
1.	2022-23	
2.	2023-24	
3.	2024-25	
	Average Annual Turnover	

UDIN No.:

Authorised Signatory
(Power of Attorney holder)

Date:

Statutory Auditor
(Stamp & Signature)

Annexure-6

Format for Financial Requirement - Net Worth Certificate

NIB No: 03/JREDA/OFFGRID/RC/26-27

To,

The Director,
Jharkhand Renewable Energy Development Agency
3rd Floor, S.L.D.C. Building,
Kusai Colony, Doranda,
Ranchi - 834002

Dear Sir,

Sub: Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand

Sir,

This is to certify that Net worth of _____ {insert the name of Bidding Company}, as on 31st March 2025 is Rs _____. The details are appended below.

Particulars	Amount (In Rs.)
Equity Share Capital	
Add: Reserves	
Subtract: Revaluation Reserve	
Subtract: Intangible Assets	
Subtract: Miscellaneous Expenditure to the extent not written off and carried forward	
Losses	
Net Worth as on 31 st March 2025	

UDIN No.:

Authorised Signatory
(Power of Attorney holder)

Statutory Auditor
(Stamp & Signature)

Annexure -7

Format of Power of Attorney for Signing Bid

NIB No: 03/JREDA/OFFGRID/RC/26-27

POWER OF ATTORNEY

(To be on non-judicial stamp paper of appropriate value as per Stamp Act relevant to place of execution.)

Know all men by these presents, we.....(name and address of the registered office) do hereby constitute, appoint and authorize Mr. / Ms.....(name and residential address) who is presently employed with us and holding the position of.....

as our attorney, to do in our name and on our behalf, all such acts, deeds and things necessary in connection with or incidental to our bid for **NIB No: 03/JREDA/OFFGRID/RC/26-27** including signing and submission of all documents and providing information / Bids to Jharkhand Renewable Energy Development Agency, representing us in all matters before [Insert Name], and generally dealing with Jharkhand Renewable Energy Development Agency in all matters in connection with our bid for the said Project.

We hereby agree to ratify all acts, deeds and things lawfully done by our said attorney pursuant to this Power of Attorney and that all acts, deeds and things done by our aforesaid attorney shall and shall always be deemed to have been done by us.

For

_____Signature (Name, Designation and Seal)

Accepted by

..... (Signature) (Name, Designation and Seal)

(Name, Title and Address of the Attorney)

Note: The mode of execution of the Power of Attorney should be in accordance with the procedure, if any, lay down by the applicable law and the charter documents of the executants (s) and when it is so required the same should be under common seal affixed in accordance with the required procedure.

Annexure-8

Details of Orders Received and Executed in Last 7 Years

NIB No: 03/JREDA/OFFGRID/RC/26-27

Details of Orders Received & Executed as per NIB for Govt. Organization during Last Seven Years.

SL. No.	Name of Agency / Organization	Purchase Order No., Date & Ordered Qty.	Date of commissioning and full execution with letter no. & date of the performance certificate	Page number of the Work order/ purchase order submitted	Page number of the performance certificate/ Work Completion certificate

Yours faithfully,

(Signature of Authorized Signatory)

Name:

Designation:

Company Seal:

Note:

- (a) Attach Photocopies of Purchase Orders and Work Completion Certificates.
- (b) Attach Photocopies of Certificate of Satisfactory Performance Issued by Concerned Nodal Agency/*PSU*/ Govt. Organization
- (c) Separate sheet may be used for giving detailed information in seriatim duly signed with page number. Proof of work order/purchase order and corresponding performance certificate should be submitted/enclosed in the bid. Non submission of the work orders and corresponding performance certificate will be treated as no experience.

Annexure-9A Price Bid

NIB No: 03/JREDA/OFFGRID/RC/26-27

Sub: Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand

Cat. No.	SPV Power Plant Capacity (kWp)	Quoted quantity (kWp) (to be entered by bidder)	Rate per kWp Excluding GST and inclusive of all other taxes & charges)
1	Group "A" 1 to 10 kWp (Solar Photo voltaic Mini/Micro Grid With Battery System)		
2	Group "B" 11 TO 50 kWp (Solar Photo voltaic Mini/Micro Grid With Battery System)		
3	Group "C" 51 to 100 kWp (Solar Photo voltaic Mini/Micro Grid With Battery System)		
4	Group "D" Above 100 kWp (Solar Photo voltaic Mini/Micro Grid With Battery System)		

Note: Bidder shall participate only in one Category from Group A to D (with Battery System). Bidder will quote rate in only one category from Group A ,B,C & D (Solar Photo voltaic Mini/Micro Grid with Battery System) in BOQ otherwise quoted rate will not be considered for evaluation.

Above quoted price for **Solar Mini/Micro grid /Stand Alone systems** are complete in all respect as per Technical Specifications inclusive of all Central/State/Local taxes & duties, packing, forwarding, transit insurance, loading & unloading, transportation & other charges etc. FOR destination at any places in Jharkhand and inclusive of installation, testing, commissioning, operation & maintenance for five years, performance testing and training.

1. Certified that rates quoted for **Solar Mini/Micro grid /Stand Alone systems** are as per specifications, terms & conditions mentioned in the bid document.
2. Price will be quoted in complete numeric figure and words.
3. For each category, more than one contractor will be empaneled.
4. The offered rate should be valid for one year which may be extended as per requirement of JREDA.

(Signature of Authorized

Signatory) Name:

Designation:

Company Seal:

Annexure-9 B: Price Break up

(Need to submit in PDF file with price bid on company letterhead.)

NIB No: 03/JREDA/OFFGRID/RC/26-27

Sub: Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo Voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand.

NOTE 1) This Annexure shall be submitted in pdf format along with price bid only. In case bidder submitting this annexure in technical bid their bid shall be out rightly being rejected.**

2) For CategoryPlease fill the name of quoted category i.e. (Group A, B, C & D)

A For 1 to 10 kWp (Solar Mini/Micro Grid Plant):

S. N.	Component	Quantity	Quote Rate per kWp Excluding GST and Inclusive of all other taxes & charges)
1	Cost of SPV Modules		
2	Cost of PCU with RMS		
3	Cost of Battery (Lead Acid-VRLA/TGEL/AGM) @ 8.4VAH/Wp		
4	Module Mounting Structure (MMS)		
5	ACDB, DCDB & Junction Boxes		
6	Pole, Cables and all BoS		
7	12W LED bulb, Switchboard with two Socket point,30W AC LED light		
8	Construction of Control room of size(10x12x10) cu ft , Chain linked Fencing, all other Civil work cost		
9	Installation Cost and Power Distribution Network connection to individual HHs cost		
10	Energy Meter		
11	CMC cost (5 years)		
12	Contractor's profit as per Jharkhand Procurement policy		
13	Other Cost (Mention items)		
Total			

NOTE-. In case there is any mismatch between Price BOQ in EXCEL format and price breakup in PDF format then bid will be rejected)**

B. For 11 to 50 kWp (Solar Mini/Micro Grid Plant):

S. N.	Component	Quantity	Quote Rate per kWp Excluding GST and Inclusive of all other taxes & charges)
1	Cost of SPV Modules		
2	Cost of PCU with RMS		
3	Cost of Battery (Lead Acid-VRLA/TGEL/AGM) @ 8.4VAH/Wp		
4	Module Mounting Structure (MMS)		
5	ACDB, DCDB & Junction Boxes		
6	Pole, Cables and all BoS		
7	12W LED bulb, Switchboard with two Socket point,30W AC LED light		
8	Construction of Control room of size(15x12x10) cu ft , Chain linked Fencing, all other Civil work cost		
9	Installation Cost and Power Distribution Network connection to individual HHs cost		
10	Energy Meter		
11	CMC cost (5 years)		
12	Contractor's profit as per Procurement policy		
13	Other Cost (Mention items)		
Total			

NOTE-**. In case there is any mismatch between Price BOQ in EXCEL format and price breakup in PDF format then bid will be rejected)

C For 51 to 100 kWp (Solar Mini/Micro Grid Plant):

S. N.	Component	Quantity	Quote Rate per kWp Excluding GST and Inclusive of all other taxes & charges)
1	Cost of SPV Modules		
2	Cost of PCU with RMS		
3	Cost of Battery (Lead Acid-VRLA/TGEL/AGM) @ 8.4VAH/Wp		
4	Module Mounting Structure (MMS)		
5	ACDB, DCDB & Junction Boxes		
6	Pole, Cables and all BoS		
7	12W LED bulb, Switchboard with two Socket point,30W AC LED light		
8	Construction of Control room of size(21x20x10) cu ft , Chain linked Fencing, all other Civil work cost		
9	Installation Cost and Power Distribution Network connection to individual HHs cost		
10	Energy Meter		
11	CMC cost (5 years)		
12	Contractor's profit as per Procurement policy		
13	Other Cost (Mention items)		
Total			

NOTE-** In case there is any mismatch between Price BOQ in EXCEL format and price breakup in PDF format then bid will be rejected)

D. For Above 100 kWp (Solar Mini/Micro Grid Plant):

S. N.	Component	Quantity	Quote Rate per kWp Excluding GST and Inclusive of all other taxes & charges)
1	Cost of SPV Modules		
2	Cost of PCU with RMS		
3	Cost of Battery (Lead Acid-VRLA/TGEL/AGM) @ 8.4VAH/Wp		
4	Module Mounting Structure (MMS)		
5	ACDB, DCDB & Junction Boxes		
6	Pole, Cables and all BoS		
7	12W LED bulb, Switchboard with two Socket point,30W AC LED light		
8	Construction of Control room of size(25x20x10) cu ft , Chain linked Fencing, all other Civil work cost		
9	Installation Cost and Power Distribution Network connection to individual HHs cost		
10	Energy Meter		
11	CMC cost (5 years)		
12	Contractor's profit as per Jharkhand Procurement policy		
13	Other Cost (Mention items)		
Total			

NOTE** Need to be submit in .PDF file with price bid on company letterhead.

NOTE-** In case there is any mismatch between Price BOQ in EXCEL format and price breakup in PDF format then bid will be rejected)

(Signature of Authorized Signatory)

Name:

De

Annexure-10

Undertaking by MSEs of Jharkhand for availing preferential treatment

NIB No: 03/JREDA/OFFGRID/RC/26-27

(To be submitted in the official letter head of the company)

I/We _____ (here in after referred to as MSE bidder) being desirous of tendering for the work under the above mentioned tender and having fully understood the nature of the work and having carefully noted all the terms and conditions, specifications etc. as mentioned in the tender document, DO HEREBY DECLARE THAT

- i. The Manufacturing unit is located at.....District in the State of Jharkhand.
- ii. The Head office or Corporate Office of the unit/company/enterprise is at..... Within the territorial Jurisdiction of Jharkhand.
- iii. The unit/company/enterprise is registered with (tick):-
 - a. Directorate of industries/District Industries Center, (Copy attached).
 - b. Khadi and Village Industries Board, (Copy attached).
 - c. Directorate of Handloom, Sericulture and Handicraft of Jharkhand Govt., (Copy attached).
 - d. Industrial Area Development Authorities, (Copy attached).
 - e. National Small Industries Cooperation Ltd, (Copy attached).
 - f. Other body specified by Directorate of Industries, Jharkhand Govt. from time to time and other industrial units/enterprises which have submitted IEM and been issued Date of Production (DOP) certificate by GM, DIC/MD, Industrial Area Development Authorities Director, Industries, GoJ.
 - g. MSE having Udyog Adhar Number issued by Ministry of Micro, Small and Medium enterprises, Gol and has been duly verified, whether unit is existing / functional and doing regular production at (Specify capacity) by GM, DIC/MD, Industrial Area Development Authorities / Director, Industries, Go", (Copy attached).
- iv. The unit/company/enterprise is registered under Jharkhand Goods and Services Tax (JGST) Act-2017 or The Central Goods & Services Tax (CGST) Act 2017, (Copy attached).
- v. The unit/company/enterprise have encouraged local people in employment.
- vi. The unit/company/enterprise complies with all statutory and legal formalities of concerned regulators/ Act.
- vii. That the product/services being supplied to JREDA has been manufactured/created by the unit located in Jharkhand only and agree to submit details of batch number/date or any other identifiable tag as per prevalent practice.

(Signature of Authorized Signatory) Name:

Designation:

Company Seal:

(This bid Performa must be submitted duly signed in case separate sheet is submitted)

Annexure-11:

NIB No: 03/JREDA/OFFGRID/RC/26-27

**Certificate of Delivery of Solar Mini/Micro grid system with Distribution Network with Households
received by the Consignee/ JREDA Official as Proof of Compliance by the Supplier**

Name of Beneficiary:.....

Address of Beneficiary:.....

Place of Supply: -Panchayat.....,Village.....,Block.....District.....,GPS coordinates.....

Certified that we have received following materials and handed over to supplier for installation of **Solar Mini/Microgrid system:**

1	Nos. & Capacity of SPV Modules, Make :-----
2	Nos. & Capacity of Batteries, Make.....
3	Nos. & Capacity of PCUs, Make.....
4	Nos. of (SSL):.....
5	Nos. of Pole.....
6	No. of 12W LED bulb
7	Energy Meter (Nos. & Serial No.)
8	Other Materials.....

Date of Supply.....

Attachment :- (Geo-tag Photographs of Materials (Module, Battery, PCU, Balance of system, etc with serial Nos.) Above materials have been supplied by
M/s.....

Signature & Seal of Supplier

Signature of Consignee along with Seal/JREDA Official:.....

Date.....

Certificate of JREDA Representative

Certified that above-mentioned materials have been inspected as per the specification and handed over to the Supplier at site for installation & commissioning.

Signature & Seal of JREDA Representative

Annexure-12

Certificate of Installation of Mini/Micro Grid System with Distribution Network with Households received from the Consignee as Proof of Compliance by the Supplier

NIB No: 03/JREDA/OFFGRID/RC/26-27

Certificate Name of Beneficiary:

Number of households benefited:____(list enclosed with Aadhar Card Number)
.....

Site Details: - Village....., Block....., District....., GPS Coordinates.....

Certified that M/s has successfully installed mini grid plant at village of total HHs. With total capacitykWp Solar Mini/ Micro Grid System and Distribution Network ofkm on dated and are in working condition since seven days:

1. Serial nos. of SPV Modules, Capacity & Make: -----
2. Serial nos. of Batteries, capacity & Make:
3. Serial nos. of PCU, capacity & Make
4. Serial nos. of LED Luminaries, Rating & Make:
5. Serial nos. of Street Light & Make:
6. Serial nos. of DCDB:
7. No. of 12W LED bulb
8. Generation Report
9. Other materials(Mentioned Items):

Attachment: Geo-tag Photographs of installed system (Three views of each component of each system)

10. Attached All Beneficiary Aadhar card details

Signature of Consignee

Signature of Supplier along with Seal

Date.....

Date.....

Signature of JREDA representative

Date.....

Annexure-13

Format for O&M and CMC Report

(Solar Mini/Micro Grid System)

NIB No: 03/JREDA/OFFGRID/RC/26- 27

[On the letterhead of Bidding Company]

To,

The Director,
Jharkhand Renewable Energy Development
Agency 3rd Floor, S.L.D.C. Building,
Kusai Colony,
Doranda,
Ranchi –
834002.

Sub: Rate Contract for Design, Manufacture, Testing, Supply, Installation & Commissioning of Solar Photo voltaic Mini/Micro Grid System of different capacities/HHs with distribution network including control room & connection to households including five years Comprehensive Maintenance Contract (CMC) on Turnkey basis in different villages anywhere in the state of Jharkhand

Sir,

Date of Installation.....

JREDA Dispatch Order No..... Dated.....

Place of Supply.....

Name of Technicians:

S.N	Place of Installed System	System Details	Date of Site Visit/ CMC	Fault observation	Fault repaired	Status of the system
1	Panchayat..... Village..... Block..... District.....	Module No.				
		Battery No.				
		PCU				
		Other BoS				
2	Latitude.....	RMS/Data logger system working or not				
3	Longitude.....	Total generation for the month in kWh:				
4		CUF for month in %:				
5		RMS login id: Password:				

*Provide Details of any replacement of systems/components, damages, plant /Inverter shut down, (Planned/forced, breakdown, etc under remarks
* Daily Register is to be maintained by the Bidder at each Solar off-grid Plant Location
*Enclosed-Monthly Generation Data as per Annexure 19

(Signature of Consignee)

Name:

Designation:

Seal:

Signature of JREDA representative

Signature of Authorized Signat

Annexure-14

Performance Guarantee Testing Report format

NIB No: 03/JREDA/OFFGRID/RC/26-27

This is to certify that the Solar Mini/Micro Grid System in village.....
Block

Districtis working satisfactory for the following parameters:

- 1.
- 2.
- 3.
- 4.

Further, the following installations/structures were found in satisfactory working order

- 1.
- 2.
- 3.
- 4.

It is also certified that the Successful Bidder provided power hours per day for days every month from the date of commissioning of the plant.

Signature of Consignee

Date.....

Signature of Supplier along with Seal

Date.....

Signature of JREDA representative

Date.....

Annexure-15

Warranty Card

NIB No: 03/JREDA/OFFGRID/RC/26-27

(To be submitted in the official letter head of the company during the supply of the materials)

1.	Name & Address of the Manufacturer/ Supplier of the System		
2.	Name & Address of the Purchasing Agency		
3.	Date of Supply of the System		
4.	Details of PV Module(s) Supplied in the System		
	(a)	Name of the Manufacturer	
	(b)	Make	
	(c)	Model	
	(d)	Serial No.	
	(e)	Wattage of the PV Module(s) under STC	
	(f)	Guarantee Valid Up To	
5.	Details of Battery		
	(a)	Name of the Manufacturer	
	(b)	Make	
	(c)	Model	
	(d)	Batch/Serial No(s).	
	(e)	Month & Year of Manufacture	
	(f)	Rated V & AH Capacity at C/20 or C/10 Rated at 27°C	
	(g)	Guarantee Valid Up To	
6.	Details of Electronics & Other BOS Items		
	(a)	Name of the Manufacturer	
	(b)	Make	
	(c)	Model	
	(d)	Serial No(s).	
	(e)	Month & Year of Manufacture	
	(f)	Guarantee Valid Up To	
7.	Designation & Address of the Person to be Contacted for Claiming Warranty Obligations		

(Signature of Authorized Signatory with Name Designation & Company Seal)

Filling Instructions:

2. The Mini/Micro Grid with Distribution Network to Households system components will be generally guaranteed as per General Terms & Conditions. The manufacturer can also provide additional information about the system and conditions of Guarantee as necessary. The Guarantee card to be supplied with the system must contain the details of the system supplied as per format given above.
3. During the Guarantee period JREDA/users reserve the right to cross check the performance of the systems for their minimum performance levels specified in the MNRE specifications

Annexure-16

Declaration by the Bidder

NIB No: 03/JREDA/OFFGRID/RC/26-27

Name of the Agency:

Work Order No. and

Date:

Sr	District	Block	Village	Habitation	Beneficiary Name	Beneficiary Aadhar Number	category	Sign/ Thumb impression of beneficiary
1	2	3	4	5	6		8	9

1. Declaration has been taken from each proposed beneficiary that they have not been benefitted from any scheme of household electrification of Central/State Govt.
2. Above mentioned site is found clear and feasible for installation of Solar Mini/Microgrid System.
3. Above mentioned beneficiaries are belonging tocategory.(General/SC/ST/OBC/PVTGs)
4. Geo-tagged photograph of above all mention site are enclosed herewith.
5. This Declaration shall be submitted with Site survey checklist i.e **Annexure 19**

SEAL & SIGNATURE OF MUKHIYA	SEAL & SIGNATURE OF AGENCY
NAME	NAME IN FULL DESIGNATION
SEAL & SIGNATURE OF SARPANCH	
NAME	

Annexure-17

Declaration by the Bidder

NIB No: 03/JREDA/OFFGRID/RC/26-27

(To be submitted in the official letter head of the company)

I/We _____/(here in after referred to as the Bidder)
being desirous of tendering for the rate contract for work under the above-mentioned tender and having fully understood the nature of the work and having carefully noted all the terms and conditions, specifications etc. as mentioned in the tender document, DO HEREBY DECLARE THAT

Sr. No.	Particulars	Name of Group quoted by bidder	Quoted Quantity/Capacity (kWp)	Type of Bidder (General/MSEs /NEW MSEs
1	Bidder Quoted for Solar Mini Grid Category (Group A or Group B or Group C or Group D)			

NOTE**

- a. The bidder will quote in only one Group from Group A, B, C & D. If the bidder will quote in more than one category from Group A, B,C & D ,then bidder shall be liable to disqualification.
- b. The bidder shall submit all valid Test certificate accordingly as per NIB terms & Conditions.
Bid will be evaluated only for the applied category and no further claim for the change of category (Gen/MSE/New MSE) will be accepted.

(Signature of Authorized Signatory)

Name:

Designation

Annexure-18
(Monthly Generation Data)

NIB No: 03/JREDA/OFFGRID/RC/26-27

Name of Agency-															
NIB NO.....															
Work Order Details.....															
Energy Generation from the Off-Grid Solar PV Power Plant for Month of															
Sl No.	District	Block	Village	Date of Installation	Capacity (kWp)	Latitude	Longitude	Name of Local Technician	Technician Mobile Number	Solar Energy Generation				Remarks	
										Previous Month Reading		Present Month Reading			Unit Generated (Kwh)
										Reading (KWH)	Date	Reading (KWH)	Date		
1															
2															
3															
4															

(Signature of Authorized Signatory)

Name:

Designation

**Annexure-19
(Solar Mini/Micro grid Site Survey Checklist)**

NIB No: 03/JREDA/OFFGRID/RC/26-27

1	Name of the village	
2	Census Code	
3	Name of the Panchayat	
4	Name of the Block	
5	Name of District	
6	Village Latitude	
7	Village Longitude	
8	No. of Total Households (HHs)	
9	Available Land Area in village (in Square feet) For 1 kWp Solar Minigrid Plant with Control Room (min 275 sqft)	
10	Village Population (As per Survey)	
11	Geo-tag site Photographs (Attached 4-5 Photographs)	
12	Accessibility & Infrastructure:-	
	I. Mobile Phone Service Network available in village (Y/N) If yes Name of Telecom Company	
	In case of non-availability of cellular network, the agency shall submit a declaration confirming the unavailability of cellular network.	
	II. Nearest Railway station(km)	
	III. Nearest Police station (km)	
	IV. No. of school with Room	
	V. No. of PHC/CHC	
	VI. No. of Anganwadi Building	
	VII No. of Temples/Worship places	
III. Any Other Community Building		
13	Whether Houses are close together or scattered	
14	Whether source of water readily available for the site (Y/N)	
15	Whether approach Road is available up to the site	
16	Village Distance from nearest JBVNL Substation (in Km)	
17	Total No. of Solar Street Light required with location	
18	Nearest Electrified village distance (in km)	
19	Fuel used at Present for lighting purpose	
20	Name of major Livelihood Activity	
21	Average HHs Annual Income (INR)	
22	Mukhiya Mobile No.	
23	Panchayat Secretary Contact No.	
24	Block Development Officer Contact No.	
25	Enclosure (Gram Sabha ,DPR & Annexure 16)	

(Signature of Authorized Signatory)

Name:

Designation